



Request For Quotation

Description : RFQ-004121 - DropOff Area Gate 04
Date of Issue : 14 Oct 2026
Date of Submission of Quotation : 21 Oct 2026 11:00:00 AM
Place of Delivery : Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone : Purchase Department IBA Main Campus, University Road, Karachi.
033237604989 Extension : 2150

Site visit will be held on Monday October 19, 2026 at 3:30 PM IBA Main Campus

Sr#	Description	Quantity
1	DropOff Area Gate 04 As per BoQ Drawing is attached SST 8% will be applicable on total amount Note: All bidders are requested to quote their amount item wise as per below details.	1 Job

B.O.Q Item	Description	Unit	Quantity
1	Soil Removal		
	removal of soil including digging to the required depth and dimensions, loading, transportation, disposal of excavated soil at an approved location, including all labour, tools, equipment, dressing and leveling of excavation, complete in all respects as directed by the Engineer.	P.Cft	1,375
2	Kerb Block Shifting		
	Carefully dismantling existing kerb stones and re-fixing them at the new alignment behind the existing line, including loading, shifting, proper alignment, leveling, haunching and benching , complete in all respects as directed by the Engineer.	Rft	125
3	Paver Fixing		
	Providing & fixing cement paving blocks flooring fairface surface finished having size of 197 x 97 x 80 (mm) of (city pavers) shape with natural colours, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand over a bed of 2" thick hill sand or stone dust and laying and compacting in specified manner/ pattern and design etc complete.(PSI 5000 to 8500) MAKE: Envicrete or Banu Mukhtar (surface finished)	Sft	563



Request For Quotation

4	Paver Fixing (Red Pigments)		
	Providing & fixing cement paving blocks flooring fairface surface finished having size of 197 x 97 x 80 (mm) of (city pavers) shape with natural colours, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand over a bed of 2" thick hill sand or stone dust and laying and compacting in specified manner/ pattern and design etc complete.(PSI 5000 to 8500) MAKE: Envicrete or Banu Mukhtar (surface finished)	Sft	250
5	Flexo Cat Eye Road Stud Fixing		
	Supply and installation of raised pavement markers (Cat's Eyes), size 80x100x20mm, made of heavy-duty aluminium alloy/ABS plastic (min. 20-ton load capacity). Features polycarbonate retro-reflective lenses (uni/bi-directional). Includes surface preparation, epoxy adhesive/bitumen bonding, and mechanical anchoring at 1.0m to 2.0m spacing along parking boundaries, complete as per project drawings and engineer instructions.	Nos	50

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/ denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.