



Request For Quotation

Description : RFQ-002159 - RENOVATION OF PARKING AREA AT ADAMJEE ACADEMIC BLOCK IBA MAI
Date of Issue : 4 Sep 2024
Date of Submission of Quotation : 9 Sep 2024 11:00:00 AM
Place of Delivery : IBA Karachi, Main Campus, Karachi
Contact Person & Telephone : Purchase Department IBA Main Campus, University Road, Karachi.
03122669895
Extension : 2150

Sr#	Description	Quantity + UOM
1	RENOVATION OF PARKING AREA AT ADAMJEE ACADEMIC BLOCK IBA MAIN CAMPUS BOQ and Drawing attached Prices are inclusive SST Site Visit is Mandatory before submission of quotation	1.00 EACH

Bill of Quantity

S.#	DESCRIPTION	QTY.	UNIT
1	Removal of Pavers		
	Removal of Existing pavers, stackup it for reuse and removal of debris from site including the cartage as per direction of Engineer In-Charge	1929.38	Sft
2	Dismatling of CC Floor		
	Dismatling of existing cc floors (1:3:6) and shifting outside the premises or allocated space as per direction of Engineer In-Charge	42.50	Cft
3	Re-Fixing of Pavers		
	Refixing in position of existing pavers present at site including removal, shifting, laying, levelling, compaction of stone dust laid in approved pattern and as directed by Engineer.	1534.50	Sft
4	P.C.C Floor		
	Cement concrete plain (1:2:4) floor including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering laid in panels complete in all respect and as directed by the Engineer	97.21	Cft



Request For Quotation

5	Kerb Block		
	Providing, laying in position 18"x12"x6" Kerb Block min 3000 PSI cylindrical strength conc. Manufactured by Banu Mukhtar, Envicrete, Megncrete or as approved by Engineer Incharge including excavtion, Concrete 1:2:4 benching etc complete as per specification.	160.00	RFT
6	Paint on Kerb Block		
	Providing & laying Black & Yellow colour Enamel Paint manufactured by Berger or ICI in two coats on Kerb Block as per direction.	500.00	Sft
7	4" dia uPVC Nikasi Pipe		
	Supply and lay 4" dia UPVC pipes of Pak Arab/ Steelex (SDR-41), Nikasi for soil, waste and vent system including specials such as tees, bends, plugs, reducers, etc. with solvent cement jointing / rubber ring push fit jointing method including cutting holes in masonry or concrete in walls, floor and in slab, making good the same, complete in all respect as per drawing, specification and as directed by the Engineer.	220.00	Rft

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate I item cost is final and no change what so ever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. Competent Authority reserves the right to change/ alter I remove any item or article or reduce I enhance quantity without assigning any reason.
9. Invoice/Bill to be submitted to Purchase Department.
10. Advance Payment subject to Bank Guarantee.
11. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates I denomination of Purchase Order.
12. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.