

**RFQ**

DESCRIPTION: **LANDSCAPING – IBA MAIN CAMPUS**  
DATE OF ISSUE: 13 August 2015  
DATE OF SUBMISSION: 15 August 2015  
PLACE OF WORK: IBA MAIN CAMPUS  
CONTACT PERSON: AZFAR ABBASI (SR EXECUTIVE R & M)

S#	Description	Approx QTTY	Rates	Amount(Rupees)
1	Digging and / Clearing / removing disposal of of any surplus of Construction Material / rubble from Sites as well as Preparation of ground for grass plantation in required line complete in all respect as per drawings specifications & as directed by General Maintenance Department	10000 sq. ft.		
2	<b>Sweet Earth Fill</b> - stacking and spreading garden soil sweet earth up to required depth and level including breaking of clods, dressing time for grassing, complete as per drawings specifications and instructions of the General Maintenance Department	10000 sq. ft.		
3	<b>Manure Fill</b> , stacking and spreading manure of 1-2" thickness over sweet earth including breaking of clods and removing of debris etc, complete as per drawings, specifications and instructions of the General Maintenance Department	10000 sq. ft.		
4	<b>Dhakka Grass</b> -Planting Dhaka grass at 2- 3" apart, including, maintenance of grass for a period of 15 days from the date of plantation, complete as per drawings, specifications and instructions of the General Maintenance Department	10000 sq. ft.		
5	Providing, approved quality garden soil sweet earth free from salt, pebbles & grass roots etc) Dumper load of 500 cu ft (manghopir origin)	8 dumpers		
6	Providing Manure KMC (ojhri) full Dhakka truck load	4 trucks		
7	Providing Champa flower Plant of Different colors of the height of 6 ft and above in 24 inch pots	10 plants		
Total Amounts (with or without Taxes please mention)				

**Terms and Conditions:**

- Material / quantities of this order is subject to final inspection at the time of delivery and calculations
- IBA reserve the right to cancel any or all of the above the above items if work / material is not in accordance with our specifications or if the delivery is delayed
- Payment will be made through crossed cheque after the receipt of the bill and delivery of material/works
- Penalty @ of 2 % per month on actual will be imposed in delayed delivery
- The rate / item cost is final and no change what so over will be accepted
- Govt tax (es), levy (ies) and charges will be charged at actual as per SRO
- Competent Authority reserves the right to change / alter / remove any item or article reduce / enhance quantity without assigning any reason
- Invoice / Bill & work order etc should be submitted to Finance Department
- Advance Payment subject to Bank Guarantee preferably National Bank of Pakistan

- No subletting in any case / items / form will be allowed
- That upon termination of this agreement the contractor shall be permitted to remove all its devices and equipment which may have been placed at premises from the time to time
- All Government taxes (including income tax and stamp duty), levies and charges will be charged as per applicable rates / denomination of work order
- Stamp Duty @ 0.3 % against total value of work order will be levied accordingly.

