



Request For Quotation

Description	: RFQ-003682 - SKM chiller & AHUs pipes cladding with insulation work-Apr26
Date of Issue	: 22 Apr 2026
Date of Submission of Quotation	: 27 Apr 2026 10:00:00 AM
Place of Delivery	: Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone	: Purchase Department, IBA Main Campus, University Road, Karachi. 021-38104700 Extension : 2153

Sr#	Description	Quantity + UOM
1	<p>Cladding Works G.I sheet 26gauge; Scope of work for SKM Chiller & AHU#11&12 chilled water pipe lines cladding works.</p> <ul style="list-style-type: none"> * Removed damage or rusted existing G.I sheet cladding from pipelines. * Remove deteriorated insulation material and dispose of it safely according to site safety guidelines. * Inspect all exposed chiller pipelines for signs of corrosion, leakage, weakening, or deformation. * Replace pipeline sections of different diameters where required to restore complete system integrity. * Repair or reinforce M.S. pipe-support stands where corrosion or damage is detected. * Clean surface rusts from pipelines and M.S. supporting structures. * Ensure surfaces are free from rust, dust, grease, and moisture before painting and insulation works. * Apply Red Oxide Primer (approved brand) to all cleaned pipelines and MS stands. * Ensure a uniform coat is applied to achieve complete rust protection as per IBA engineering requirements. * Where necessary, apply additional protective coating to enhance durability. * Supply and install 26-gauge G.I sheet for external cladding of insulated pipelines. * Fabricate sheets to match pipeline sizes and routing. * Fix sheets using stainless-steel screws/rivets * Ensure all installed G.I cladding is aligned, sealed, and free from sharp edges. * Clean working areas and remove all waste, scrap, and debris generated during work. * Repair and installation of G.I sheet cladding (26 gauge) on all chiller pipelines. * Pipeline replacement (where required). * Anti-corrosive red oxide coating. * Complete installation meeting IBA specifications. * Safety-complaint and fully restored pipeline system. * Submit a final inspection report and hand over work to the client. <p>Note: Site visit is must Location: City Campus, Garden Kiyani Road. POC: Qamar sb</p>	1,160.00 SQR FT



Request For Quotation

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.