

Request For Quotation

Description : RFQ-003943 - Girls Hostel Paver Installation
Date of Issue : 12 Aug 2026
Date of Submission of Quotation : 18 Aug 2026 11:00:00 AM
Place of Delivery : Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone : Purchase Department IBA Main Campus, University Road, Karachi.
03323760498 - Extension : 2150

Site visit will be held on Monday August 17, 2026 at 3:00PM IBA Main Campus

Sr#	Description	Quantity + UOM
1	Girls Hostel Paver Installation 8% SST applicable	1 Job

B.O.Q Item	Description	Unit	Quantity
1	Excavation & Backfilling		
	Excavation and Backfilling in all kinds of sub-surface materials (soft/rock) upto any depths including disposal of surplus/rejected excavated materials to designated places at any lift.	P.Cft	1,244
-			
2	External Plaster on Situ wall	-	
	Providing and laying plaster with cement sand mortar with G.I. expanded metal lathe at the interfaces of structures of different materials including staging and curing complete in all respect and / or as directed by the Engineer.		
a	3/4" thick, 1:4 cement sand plaster to exterior surface.	P.sft	424
-			
3	Paving Block(Red Pigmented)		
	Providing & fixing cement paving blocks flooring fairface surface finished having size of 197 x 97 x 80 (mm) of (city pavers) shape with red colours, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand over a bed of 2" thick hill sand or stone dust and laying and compacting in specified manner/ pattern and design etc complete.(PSI 5000 to 8500) MAKE: Envicrete or Banu Mukhtar (surface finished)	P.Sft	277.00



Request For Quotation

4	Paving Block(Natural Colour)		
-	Providing & fixing cement paving blocks flooring fairface surface finished having size of 197 x 97 x 80 (mm) of (city pavers) shape with natural colours, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand over a bed of 2" thick hill sand or stone dust and laying and compacting in specified manner/ pattern and design etc complete.(PSI 5000 to 8500) MAKE: Envicrete or Banu Mukhtar (surface finished)	P.Sft	1,322.00
-			
5	Kerb Stone(Natural Colour)		
-	Providing & fixing Precast Edge Block 3750 PSI Industrial Made Size 6 inches thick x 12 inches long x 18 inches high including the cost of Cartage, excavation, form Work for haunching, 1450 PSI lean concrete, 2250 PSI concrete for haunching, 1:4 cement sand mortor. MAKE: Envicrete or Banu Mukhtar (surface finished)	P.Rft	26.40

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/ denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.