



Request For Quotation

Description	: RFQ-003546 - Emergency Staircase at Old Girl's Hostel
Date of Issue	: 2 Mar 2026
Date of Submission of Quotation	: 10 Mar 2026 11:00:00 AM
Place of Delivery	: Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone	: Purchase Department IBA Main Campus, University Road, Karachi. 03323760498 Extension : 2150

Sr#	Description	Quantity + UOM
1	Emergency Staircase at Old Girl's Hostel Details as per BOQ Site Visit will be held on March 05, 2026 at IBA Main Campus	1 Job

Steel Spiral Stair Case at Old Girl's Hostel

S#	Description	Qty	Unit	Rate	Amount
1	Dismantling Precast Cement Concrete Spiral Stair Case (32 feet height).	2	Job		
2	Excavation in shingle or gravel formation and rock in dry not requiring blasting undressed lead upto 100ft.	32.00	Cft		
3	Providing & Erection of 3'-0" dia spiral steel stair case with 4" dia M.s Pipe, 14 guage step plate, Angle iron 1-1/2" x 1" , landing on each floor (03 nos). Including painting with 01 coat of Redoxide and 02 coat of enamel paint complete etc. (32 feet Height)	2	nos		
4	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering. Ratio. 1: 4 :8	16	Cft		
5	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Grade 60	0.57	Cwt		



Request For Quotation

6	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds, lifting, centering, shuttering and curing. (including screening and washing of shingle. R.C.C work in roof slab, beams, column, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects. (i) Ratio 1 : 2: 4 90 Lbs of cement, 2 Cft sand and 4 Cft shingle 1/8" to 3/4" gauge.	32	Cft		
Sub-total					
8% SRB					
Total Amount					

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/ denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.