

## Scope of Work

S #	Description	Qty	Unit	Location
1	Fixed Aluminum Partition			
	Providing and fixing fixed Window comprising of 2 mm thick best quality natural anodized (champagne color) aluminum section from Pakistan Cables or equivalent using 5 mm glass including standard hardware, gasket, silicon, wastage etc. complete in all respect	2x4	Sq ft	Testing Services Department
2	Window Blinds			
	Provide and install horizontal fabric window blinds of approved sample (thermic or approved equivalent) including lifting and fixing etc. complete in all respect	2x4	Sq ft	Testing Services Department
3	Fixed / Open able Aluminum Partition/ window			
	Providing and fixing partly fixed and partially open able Window comprising of 2 mm thick best quality natural anodized (champagne color) aluminum section from Pakistan Cables or equivalent using 5 mm glass including standard hardware, gasket, silicon, wastage etc. complete in all respect	2x8	Sq ft	Security Services Department
4	Dismantling and Plastering Block Masonry			
	<p>a. Dismantling / cutting / removal of existing masonry walls, including removal of debris from site etc complete in all respect as per site requirements</p> <p>b. Providing and applying cement and sand plaster (1:6) to walls etc., making edges and corners for fixing Aluminum structure including preparation of surface before plastering finishing curing etc complete in all respect</p>	2x4	Sq ft	Testing Services Department
5	Dismantling / Replacing Old Indian WC with Commode			
	<p>a. Dismantling / cutting / removal of existing tiles and providing / fixing the same on site tiles of same quality, color and type, after removal of Asian WC and making good surface with above specified tiles for placing Commode complete in all respect as per site requirements including all related materials</p> <p>b. Providing and fixing Western / English WC one piece type (Porta or equivalent color white) with commode seat, flush tank, including fittings, thimble, making all joints to services and drains; plugging and screwing as necessary to the structure complete in all respect as per site requirement after removal of existing Asian WC</p>	1	job	Testing Services Department