

Request for Quotation

(Works)

Description : 0045/0016 - Passive Cabling Work

Date of Issue : 20-Oct-17 12:50 PM
Date of Submission of Quotation : 26-Oct-2017 02:30 PM

Place of Work : Main Campus

Contact Person & Telephone : Purchase Department, IBA Main Campus,

+922138104700, Ext 2150, 2152

Sr#	Description	Specification	Quantity / Job
1	UTP Cabling, Ducting, Piping, Termination, Tagging, Proper Cable harnessing / organizing & rack installation with All Materials At Fauji Foundation Building	80 feet 3M Volition Cat 6 Cable, UTP,PVC 4-pair UTP cable, exceed TIA/EIA-568-B.2-1 1 meter 3M Volition Cat 6 RJ 45 to RJ 45 Patch Cable, UTP,PVC	1
2	UTP Cabling, Ducting, Piping, Termination, Tagging, Proper Cable harnessing / organizing & rack installation with All Materials At 2nd Floor Aman CED Building	80 feet 3M Volition Cat 6 Cable, UTP,PVC 4-pair UTP cable, exceed TIA/EIA-568-B.2-1 1 meter 3M Volition Cat 6 RJ 45 to RJ 45 Patch Cable, UTP,PVC	1
3	UTP Cabling, Ducting, Piping, Termination, Tagging, Proper Cable harnessing / organizing & rack installation with All Materials UTP Fluke testing (Fluke Analyzer DTX-1800) At IBA Girls Hostel	330 feet 3M Volition Cat 6 Cable, UTP,PVC 4-pair UTP cable, exceed TIA/EIA-568-B.2-1 4 meters 3M Volition Cat 6 RJ 45 to RJ 45 Patch Cable, UTP,PVC 2 units 3M Volition RJ45K6 Jack, Cat 6, UTP, T568A/T568B Wiring, Unshielded 1 unit 3M Volition UK Single Gang Faceplate, 2 port, w/o shutter, with 3M logo (White)	1



Request for Quotation

(Works)

4	UTP Cabling, Ducting, Piping, Termination, Tagging, Proper Cable harnessing / organizing & rack installation with All Materials UTP Fluke testing (Fluke Analyzer DTX-1800)	400 feet 3M Volition Cat 6 Cable, UTP,PVC 4-pair UTP cable, exceed TIA/EIA-568-B.2-1 8 meters 3M Volition Cat 6 RJ 45 to RJ 45 Patch Cable, UTP,PVC	1
	At IBA Boys Hostel	4 units 3M Volition RJ45K6 Jack, Cat 6, UTP, T568A/T568B Wiring, Unshielded 2 units 3M Volition UK Single Gang Faceplate, 2 port, w/o shutter, with 3M logo (White)	

Terms & Conditions:

- 1. Sales tax registration certificate with last month return copy (FBR and / or SRB) must be provided at the time of submission of quotation.
- 2. Work of this order is subject to final inspection at the time of completion.
- 3. We reserve the right to cancel any or all the above work if it is not in accordance with our specification or if the delivery is delayed.
- 4. Payment will be made through crossed cheque after the receipt of the bill and completion of the above work.
- 5. General Sales Tax will be paid on applicable items only.
- 6. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
- 7. The rate / item cost is final and no change what so ever will be accepted.
- 8. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
- 9. Competent Authority reserves the right to change / alter / remove any item or article or reduce / enhance quantity without assigning any reason.
- 10. Invoice should be submitted to Finance Department.
- 11. Advance Payment subject to Bank Guarantee preferably National Bank of Pakistan.
- 12. No subletting in any case / item / form will be allowed.
- 13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates / denomination of Work Order.
- 14. Stamp duty 0.25% for works against total value of Work Order will be levied accordingly.
- 15. IBA, also reserve the right to issue Work Order for any single items to different lowest responsive bidders or issue Work Order for all the items to any lowest responsive bidder.