

Request For Quotation

Description : RFQ-003133 - STP Process Tank Cleaning, Paint Work and Disposal
Date of Issue : 23 Sep 2025
Date of Submission of Quotation : 01 Oct 2025 11:00:00 AM
Place of Delivery : Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone : Purchase Department IBA Main Campus, University Road, Karachi.
03323760498 Extension : 2150

Sr#	Description	Quantity + UOM
1	STP Services Special Instruction: 1. Mandatory Site visit will be held on Monday September 29, 2025 at 11am 2. Sludge will be removed from the site in sucker bowser will be disposed properly by the contractor. 3. All the material and activities essential to complete the job will be the responsibility of the contractor. 4. Job Completion Time – 15-days.	1 Job

CLEANING & PAINTING PROCESS TANK OF STP (ONE JOB)

S #	Description	Unit	Rate	Total Amount
1	STP-Process Tank(Including Lamella Clarifier and Buffer tank) Cleaning and Painting Work including the following: <ul style="list-style-type: none"> Septic Tank Plant Cleaning through Sucker Bowser – STP Painting, Collection, Transportation & disposal at IBA main campus. STP Septic Tank Sizes in feet <ul style="list-style-type: none"> i. Sewerage Treatment plant. Size: 28 X 11 X 11 FT = 3340 Cubic ft ii. UG holding Tank # 2 Size: 12 X 35 X 16 FT = 6720 Cubic ft iii. Unnamed Tank Size: 5 X 5 X 16 FT = 400 Cubic ft iv. US Storage Irrigation Tank # 1 Size: 17.5 X 20 X 12 FT = 4200 Cubic ft Waste Disposal Procedure/Techniques STP waters from designated 4 Tanks will be removed through Bowser along with sludge-Waste water shall be disposed to designated plant/area in Karachi. 1. STP 1 - Shall be cleaned inside & painting after removal of water/sludge 2. STP II, iii & iv - Waste water shall be removed 3. Manpower/Machineries from Contractor <ul style="list-style-type: none"> Rates inclusive of Labor & transportation 1. Sucker bowser 2. STP Grinding and Epoxy paints (Applying 1-coat of High Built Zinc Rich Epoxy Primer. Thickness 200 microns)	1 Job		



Request For Quotation

	3. Applying 2 coats of coal tar Epoxy C-200. Thickness 400 microns 4. Proper disposal of sewerage water and sludge from holding tank during the cleaning of process tank Cost of all the prerequisite material and activities to complete the job must be included in the price.			
Total Amount – PKR				
SST				
Grand Total Amount Including All Tax – PKR				

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/ denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.