



# Request For Quotation

**Description** : RFQ-002653 - Signages-Mar25

**Date of Issue** : 3 Apr 2025

**Date of Submission of Quotation** : 8 Apr 2025 12:00:00 AM

**Place of Delivery** : Stores, IBA Main Campus, University Road, Karachi.

**Contact Person & Telephone** : Purchase Department, IBA Main Campus, University Road, Karachi.  
021-38104700  
Extension : 2153

Sr#	Description	Quantity + UOM
1	<p>Signage Traffic Signage Circular; 24"; Speed Limit Signage</p> <p>Providing &amp; fixing of Circular size upto 2' Dia made of DM Engineering Grade prismatic lamination on 17 gauge G.I sheet with 16 gauge 8 ft G.I pipe of 2" dia. The pipe shall be embedded 2 ft under floor with excavation, filling &amp; concreting in 1:2:4 ratio complete in all respect.</p>	3.00 EACH
2	<p>Signage Traffic Signage; 24"x24"; Zebra Crossing Signage</p> <p>Providing &amp; fixing of Traingular size upto 2' x 2' made of DM Engineering Grade prismatic lamination on 17 gauge G.I sheet with 16 gauge 8 ft G.I pipe of 2" dia. The pipe shall be embedded 2 ft under floor with excavation, filling &amp; concreting in 1:2:4 ratio complete in all respect.</p>	1.00 EACH
3	<p>Signage Traffic Signage; 24"x24"; Right Curve Signage</p> <p>Providing &amp; fixing of Traingular size upto 2' x 2' made of DM Engineering Grade prismatic lamination on 17 gauge G.I sheet with 16 gauge 8 ft G.I pipe of 2" dia. The pipe shall be embedded 2 ft under floor with excavation, filling &amp; concreting in 1:2:4 ratio complete in all respect.</p>	3.00 EACH
4	<p>Signage Traffic Signage; 24"x24"; Left Curve Signage</p> <p>Providing &amp; fixing of Traingular size upto 2' x 2' made of DM Engineering Grade prismatic lamination on 17 gauge G.I sheet with 16 gauge 8 ft G.I pipe of 2" dia. The pipe shall be embedded 2 ft under floor with excavation, filling &amp; concreting in 1:2:4 ratio complete in all respect.</p>	2.00 EACH
5	<p>Signage Traffic Signage; 24"x24"; U-Turn Not Allowed Signage</p> <p>Providing &amp; fixing of Traingular size upto 2' x 2' made of DM Engineering Grade prismatic lamination on 17 gauge G.I sheet with 16 gauge 8 ft G.I pipe of 2" dia. The pipe shall be embedded 2 ft under floor with excavation, filling &amp; concreting in 1:2:4 ratio complete in all respect.</p>	1.00 EACH



# Request For Quotation

## **Terms & Conditions :**

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.