



Request For Quotation

Description : **RFQ-003780 - Tennis Court Restoration Works**
Date of Issue : **8 Jun 2026**
Date of Submission of Quotation : **15 Jun 2026 11:00:00 AM**
Place of Delivery : Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone : Purchase Department IBA Main Campus, University Road, Karachi.
03323760498
Extension : 2150

Sr#	Description	Quantity + UOM
1	Tennis Court Restoration Works As per BoQ Site visit will be held on Thursday June 11, 2026 at 3:30PM IBA Student Center Main Campus SST 8% will be applicable on total amount Note: All bidders are requested to quote their amount item wise as per below details.	1 Job

Item No.	Description of Item	Quantity	Unit
1	Safety nets Providing, supplying and fixing of safety nets(Chain Link Fence) 2" x 2" (2.4/4mm PVC Coated) , including all necessary hooks, tying wire, clamps, and scaffolding support complete in all respects as required at site.	2,160.0	Rft
2	Removal of existing Fence Carefully dismantling and removal of existing Mild Steel (MS) fence including posts, rails, mesh/grill, cutting (if required), making good of disturbed surfaces, and shifting of dismantled material to designated location or disposal outside premises as directed by Engineer	2,160.0	Kg
3	Epoxy Paint on Ms Frame Supply and apply one coat of primer and two coats Metal Epoxy paint finish of Master Paints or equivalent or approved quality on MS Columns & other structure by using Airless Spray in approved shades, prior to application all surface generally must be clean, dry, free from all defective or poorly adhering material, dirt, and grease etc, complete in all respect as directed by Engineer and as per manufacturer's recommendations. Airless Spray tip 13 thou, 2000 psi Epoxy Paint should be applied over a suitable primer or build coat. For recoating, the underlying system should be intact, sound and undamaged. Ensure that the surface to be over-coated is clean, dry, free from dust, grease and oil, or any other surface contaminants. Wash surface using fresh water to remove soluble salts. Always ensure to follow the maximum over-coating time for the primer/build coat and it should not be exceeded prior to application. The rate shall include all labor, materials, tools, scaffolding, and surface cleaning. Minimum total dry film thickness: 220 microns. (Suitable Primers: Master Epoxy Z.P Primer or equivalent)	1,888.2	sft
4	Welding repair works Welding repair work on damaged / rusted / hollow MS sections including cutting of damaged portion, welding, grinding, touch-up and strengthening complete in all respects where required	1.0	job



Request For Quotation

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/ denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.