



Request For Quotation

Description	: RFQ-002710 - 8786 - Optical Fiber Laying Work
Date of Issue	: 25 Apr 2025
Date of Submission of Quotation	: 30 Apr 2025 12:00:00 PM
Place of Delivery	: Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone	: Purchase Department, IBA Main Campus, University Road, Karachi. 0322-3553032 Extension : 2155

Sr#	Description	Quantity + UOM
1	MS Grill Safety grill for Access Point; - Pole angle With Grill Covering for Football & Cricket Ground WIFI. - Per unit rates required. - GST applied separately. - Any substandard work & items will not be accepted.	8.00 EACH
2	ODF Cassette Loaded with pigtails; 8 port; Desktop; - ODF 8 Port Desktop with Duplex LC - Loaded. - Per unit rates required. - GST applied separately. - Only genuine and original item/s will be accepted. - Any substandard work & items will not be accepted.	3.00 EACH
3	Communication Rack 600mmX600mm; 6 U; - With Fan - with Fitting - Per unit rates required. - GST applied separately. - Only genuine and original item/s will be accepted. - Any substandard work & items will not be accepted.	2.00 EACH
4	Fiber Optic Joint Enclosure 48 core; - Loaded - Per unit rates required. - GST applied separately. - Only genuine and original item/s will be accepted. - Any substandard work & items will not be accepted.	2.00 EACH
5	PVC Pipe (In Feet) 1*1/2"; - With Fitting Accessories. - Jeddah - Per feet rates required. - GST applied separately. - Only genuine and original items will be accepted. - Any substandard work & items will not be accepted.	120.00 FEET



Request For Quotation

6	<p>Manhole Construction</p> <p>PaverRemove,ExcvationFondation,ChamberConstruction;</p> <ul style="list-style-type: none"> - Constructing Manhole or inspection chamber internal size 2'-0" x 2'-0" x 3'-6" depth with walls of 6" thick block masonry with cement sand mortar and 1:3 CSM plaster, 1/2" thick from inside and 1" thick outside over benching and channel including fixing heavy-duty C.I. Manhole cover of GMP or equivalent brand embedded in plain CC complete as per standard specifications and as directed by engineer. - Total Lump-sum or total rates required for whole job. - SST applied separately. - Any substandard work & items will not be accepted. 	1.00 EACH
7	<p>Manhole Construction</p> <p>PaverRemove,ExcvationFondation,ChamberConstruction;</p> <ul style="list-style-type: none"> - Constructing Manhole or inspection chamber internal size 3'-0" x 3'-0" x 3'-6" depth with walls of 6" thick block masonry with cement sand mortar and 1:3 CSM plaster, 1/2" thick from inside and 1" thick outside over benching and channel including fixing heavy-duty C.I. Manhole cover of GMP or equivalent brand embedded in plain CC complete as per standard specifications and as directed by engineer. - Total Lump-sum or total rates required for each Manhole. - SST applied separately. - Any substandard work & items will not be accepted. 	4.00 EACH
8	<p>Fiber Splicing Work</p> <p>;; ;</p> <ul style="list-style-type: none"> - 74 Core fiber Splicing With ODF & Joint Enclosure Harnessing. <p>(Note: Work Included NGH TO OGH)</p> <ul style="list-style-type: none"> - Total Lump-sum or total rates required for whole job. - SST applied separately. - Any substandard work & items will not be accepted. 	1.00 EACH
9	<p>Core Cutting Work</p> <p>;; ;</p> <ul style="list-style-type: none"> - 40ft Road Cutting With Cement Filling. <ul style="list-style-type: none"> - Total Lump-sum or total rates required for whole job. - SST applied separately. - Any substandard work & items will not be accepted. - IBA reserves the rights and instruct to install the required items or work at multiple locations or at single location at IBA, Karachi. 	1.00 EACH

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery by IBA ICT department or IBA stores or end user at IBA.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made within 30 working days through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).
4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate/item cost is final, and no change whatsoever will be accepted.
7. Government tax(es), levi(es) and charge(s) will be charged at actual as per SRO.
8. IBA reserves the right to accept or reject any quotation without assigning any reason thereof.
9. IBA reserves the right to change/alter/remove any item or article or reduce/enhance quantity without assigning any reason.
10. IBA also reserves the right to issue a Purchase Order for any single item to different lowest responsive bidders or for all the items to any lowest responsive bidder.
11. Invoice/Bill to be submitted to Purchase Department.
12. Advance Payment subject to Bank Guarantee.
13. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates/ denominations of the Purchase Order.
14. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.