

Request For Quotation

Description	: RFQ-001744 - Soakage Pits at Boy's Hostel
Date of Issue	: 22 Feb 2024
Date of Submission of Quotation	: 25 Feb 2024 11:00:00 AM
Place of Delivery	: Stores, IBA Main Campus, University Road, Karachi.
Contact Person & Telephone	: Purchase Department IBA Main Campus, University Road, Karachi. 03122669895 Extension : 2150

INSTITUTE OF BUSINESS ADMINISTRATION (IBA) KARACHI			
CONSTRUCTION OF OFFICES AND STORES BUILDINGS PHASE-I AT IBA MAIN CAMPUS KARACHI UNIVERISTY ENCLAVE			
Laying of 300mm dia Sewer Pipe Lines for disposal of Boys Hostel to Mian Gate			
Sr. #	Particulars	Unit	Qty
1/1	Excavation for Sewer line / Manhole / Structure in all kinds of soils and road pavement / foot paths including all operations of site clearing , grubbing ,dewatering of sub soil water ,sewAge and other sources .Levelling , dressing and ramming the excavated surface and disposal of excated surplus material to designated disposal areas within 25 Km including Backfilling with selected excavated material from any site location including breaking clods , dressing ,watering , compacted in layer not Exceeding 150 mm thickness ,all complete as per drawing , specification and as directed by the Engineer.		
	in Common Material	cft	18,000
	in Hard Rock Excavation	cft	4,500
2/1	Providing and laying Granular fill (Granular Bedding) material from approved source for backfilling / bedding complete with breaking clods and compacted to 90% AASHTO dry density complete as per drawing , specification and as directed by the Engineer.	cft	2,500
3/1	Providing laying and jointing of various dia R.C.C pipes with Spigot Socket Joint manufactured in accordance with A.S.T.M C-76 BS 5911 including cost of sockets and rubber ring etc. Complete as per specifitions, drawing and as directed by the Engineer.		
	ii) 300 mm internal dia	Rft	1,700
4/1	Providing and Laying plain cement concrete Class 10/20 using sulphate resisting cement, in situ concrete including formwork , mixing ,pouring,levelling ,compacting , vibrating and curing complete as per drawing , specification and as directed by the Engineer.	cft	79

5/1	Providing and laying in Situ R.C.C Class C 30/20 using sulphate resisting cement in circular / Rectangular manhole, chamber and elsewhere including formwork ,mixing ,pouring ,levelling ,compacting ,vibrating and curing,complete as per drawings,specification and as directed by the Engineer (Excluding Steel reinforcement)		
	i) In Base Slab	cft	80
	ii) In Walls	cft	435
	iii) In Top Slab	cft	250
6/1	Providing and laying in plain cement concrete Class C-30/20 using sulphate resisting cement Benching of Circular manhole or else where including formwork, mixing , pouring ,levelling ,compacting ,vibrating and curing ,complete as per drawings, specification and as directed by the Engineer.	cft	75
7	Providing and laying in plain cement concrete Class C-30/20 using sulphate resisting cement Bedding / Encasement of various dia pipe including formwork, mixing , pouring ,levelling ,compacting ,vibrating and curing ,complete as per drawings, specification and as directed by the Engineer. (Provisional Quantity)	cft	50
8	Reinstatement of Asphalt Pavement Roads including SubBase course , Aggregate base and wearing course complete with compaction and as shown in drawing.	sft	850
9	Providing and applying two coats of internal epoxy coating resistance to aggressive chemicals in domestic sewers of various dia RCC pipes etc. complete as per specification,drawings and as directed by the Engineer.	sft	1,700
10	Providing laying and jointing 36inch dia Ring slab with 24inch manhole a of pre cast manhole cover of R.C.C Class C-30/20 using Sulphate Resisting Cement including formwork,mixing , pouring , levelling ,compacting , vibrating , curing , transporting ,placing ,and jointing,complete as per drawings ,specification, and as directed by the Engineer (Including the cost of steel reinforcement.)	No.	17
11	Making Interconnection with the sewer including cutting of manhole , cutting/fixing of pipe in various dia , its grouting and making good , complete as directed by the Engineer.		
	a) upto 300mm dia	Nos.	4
	b) over 300 mm dia	Nos.	4
12	Extra over Item No - 1/1 for continued dewatering after excavation and during bedding , placing concrete units or in situ concreting and back filling.	rft	1,700
13	Facilitation/ Supervision Charges	Lumsum	

Terms & Conditions :

1. Material of this order is subject to final inspection at the time of delivery.
2. We reserve the right to cancel any or all the above items if material is not in accordance with our specification or if the delivery is delayed.
3. Payment will be made through crossed cheque after the receipt of the Invoice/Bill & delivery of above item(s).



4. General Sales Tax will be paid on applicable items only.
5. Liquidity damage at the rate of 2% per month on actual will be imposed on delayed delivery.
6. The rate of item cost is final and no change whatsoever will be accepted.
7. Government tax(es), levy(es) and charge(s) will be charged at actual as per SRO.
8. Competent Authority reserves the right to change/ alter/ remove any item or article or reduce/ enhance quantity without assigning any reason.
9. Invoice/Bill to be submitted to Purchase Department.
10. Advance Payment subject to Bank Guarantee.
11. All Government taxes (including Income tax and stamp duty), levies and charges will be charged as per applicable rates of Purchase Order. I denomination
12. Stamp Duty 0.35% for Goods against total value of Purchase Order will be levied accordingly.