

**B.O.Q FOR CONCRETE FLOORING AND MAKING OF ROOF FOR STORE ROOM &
WASHING AREA**

AT NEW GIRLS HOSTEL IBA

| SNO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|------------|--|-------------|-----------------|-------------------------|---------------|
| 01 | Providing and laying 2" thick cement concrete 1:2:4 specified strength using ¾ maximum size graded coarse aggregate and fine aggregate including the cost of formwork including removal and curing completed in all respect. | Cft | 300 | | |
| 02 | Providing and fixing pre-cast slab roof. the activity includes laying of heavy-duty steel guarders and 1:2:4 concrete slabs | Sft | 540 | | |
| 03 | Providing and Fixing Iron Gate 6' x 7' Heavy Duty with oil Paint completed in all respect. | Sft | 300 | | |
| | | | | Total Amount | |