

Institute of Business Administration (IBA)

Main Campus

Project: Classroom Adamjee Building, Main Campus

Works: Dampa Ceiling Aluminium Work in Adamjee Classroom Chiller Ducting Area

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<u>Provide & Fix Dampa Ceiling Aluminium</u> Providing & fixing metal ceiling aluminium, of China make or Equivalent 2' x 2' Tiles ceiling, laid into a G.I T&L Angle 1" x 1" frame work, plump, rods, hanger clips, jointing clips, and G.I Wire, suspended from the structural ceiling, complete in all respects as per Site requirement Note: This item includes the removal of Existing Gypsum False Ceiling. Site visit is mandatory for the quotation of rates.	250.0	Sft.