

B.O.Q – CIVIL WORK AT NEW GIRLS HOSTEL IBA

CONCRETE FLOORING AND MAKING OF ROOF FOR STORE ROOM & WASHING AREA

SNO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
01	(i) Providing and laying 4" thick cement concrete Sub Floor 1:4:8 specified strength using ¾ maximum size graded coarse aggregate and fine aggregate including. (ii) Providing and laying 3" thick cement concrete Fair Floor 1:2:4 specified strength using ¾ maximum size graded coarse aggregate and fine aggregate including completed in all respect	Cu. Ft. Cu. Ft.	110 90		
02	Providing and fixing pre-cast slab roof with Guarders Plus over laying 3/8 dia steel bar 10" C/C 10" both way Average 3" thick 1:2:4 concrete.	Sq. Ft.	460		
03	Providing and Fixing MS Sheet Iron Gate 6' x 7' Heavy Duty with Red oxide & 3 coats of Enamel Paint completed in all respect.	Job	1		
04	Providing/Laying Termite Proofing using with Liquid Chemical Agenda EC-25 by drilling into Earth.	Sq. Ft.	200		
05	Providing and Fixing Rain water SP out 4"	No	1		
06	Water Proofing Providing and applying one layer of jute base felt 70lbs one layer each roll of 10square meter including the cost cost primer per manufactured and specified site condition with bonding coat of bitumen 35/100 lbs. per square feet fine marble stone chips 1/200 Sqft spreading on slab completed in all respect direct by the maintenance	Sq. Ft.	460		
	Total Amount including all taxes				