

SCOPE OF WORK

REPLACEMENT OF WOODEN FLOOR AT G&T AUDITORIUM, IBA MAIN CAMPUS

S. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Dismantling of Plank or Wooden Block Flooring.	SFT	1150		
2	Providing Anti-Termite treatment by spraying / spreading Neptachlor or Tenakil 0.5 % Emulsion as an overall preconstruction treatment in slab type construction under the slab and along attached perches or entrances etc. complete as per direction of Engineer Incharge.	SFT	1150		
3	Providing & Laying non-stick floor tiles ¼" thick porcelain, size minimum 144 Square Inch in wooden texture as per approved sample in approved make and shade (Master, Shabbier or Equivalent as approved) laid over 1-1/2" thick CSM over already laid subbase jointed with approved tile bond, curing etc, complete with all respect.	SFT	1150		
Total					
Tax					
Grand Total					