

**TABBA ACADEMIC BLOCK FIRST FLOOR STAFF ROOMS NEW**

S.No.	SPECIFICATION	UNIT	LENGTH	WIDTH	HEIGHT	QUANTITY
-------	---------------	------	--------	-------	--------	----------

**TWO ROOMS ESTIMATION AND QUANTITIES**

7	<p>DOOR FRAME AND DOOR SHUTTER FIXING Providing fixing Oakwood ply flush door of best quality with ventilator using Oak wood frame (seasoned and termite treated ) with Oak wood lipping and MS powder coated door frame and paints/polish (like existing with others door frame &amp; shutters) Including all required fixtures and fittings like locks,hinges,holdfast and polishing of approved shade etc.complete in all respect as per drawings , details and instruction of IBA Engineer.</p> <p>3'-6" x 9' including ventilator</p>	nos				2
8	<p>ALUMUNIUM WINDOWS Providing and fixing glazed Aluminium window coprizing with best quality natural anodized aluminium frame of 4" section from pakistan cable or equivalent using 5mm tinted glass including standard hardware wastage , fly mesh panels also included complete as per drawing , specificationand instructin of the Engineer.</p>					2
9	<p>Porcelain tiles flooring Providing and laying porcelain tiles of approved sample for flooring of rooms with 1:4 cement sand mortar base (minimum 2" ) of required thickness and tile bond (shabbir/equivalent) with approved grout &amp;colour as per manufacturere specification including Curing, cleaning hacking /chipping of existing surface for bonding where necessary complet in all respect ( 02 rooms)</p>	sft	10.5	13.25	2	<b>278.25</b>