

Comparative Statement
Removal of Granite Cladding Work at Aman Tower
Tender # CW/08/20-21

| | | | | M/s. Kaim Khani Construction & Builders | |
|------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----------|-----------------------------------------|--------------|
| S. No | Descriptions | Unit | Qty | Rate | Amount |
| 1 | <p>The job includes the following:</p> <p>a. Scaffolding supply, fixing, erecting working platform and then disassembling the same after completion of the job.</p> <ul style="list-style-type: none"> The system shall be erected on existing Patio at Ground level up to 5th Floor height using Scaffolding MS pipes with coupled & uncoupled jointing system strong enough to act as working platform supported properly with bracing to resist air/ wind and working pressure etc. Wooden plank for platform on MS pipes shall be placed to ensure work safety. The working platform should be shielded with green Nylon Net. The working area shall be cordoned off properly as per direction. The work men (labour) shall be equipped with necessary safety arrangements as per direction. The contractor shall submit detailed drawings, design and etc before execution of the job. <p>NB: Installation shall be carried out without causing any damage to existing floor</p> <p>b. Upon completion the scaffolding pipes and joints shall be moved outside the IBA premises.</p> | SFT | 20,000.00 | 80.00 | 1,600,000.00 |
| 2 | <p>Removal of granite tiles safely from existing cladding surface by cutting using hand grinder and the existing installed bolts & wires. The removed tiles shall be properly stacked without any damage.</p> <p>All the stacked tiles shall be promptly moved safely from IBA City Campus to the designated site at IBA Staff Town without any damage.</p> | SFT | 20,000.00 | 120.00 | 2,400,000.00 |
| 3 | Disposal of all debris outside the IBA premises. | One job | | 100,000.00 | 100,000.00 |
| IBA team shall visit the warehouse to ensure that the availability of scaffolding. | | | | | |
| Total | | | | Rs. 4,100,000.00 | |
| SST | | | | Rs. 533,000.00 | |
| Grand Total Amount | | | | Rs. 4,633,000.00 | |

MEMBER (EXTERNAL)
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
Harris Qureshi
PPR Advisor
HES

CHAIRPERSON
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
Dr. J. M. Kazi
Assistant Professor
IBA, Karachi

MEMBER
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
Syed Azeem Hussain Kazmi
Finance
IBA, Karachi

MEMBER (EXTERNAL)
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
M. Masood Khan
Admn Officer
CEM B, Uok

MEMBER
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
Majeed Zahedi
Sr. Manager II
IBA, Karachi