

INSTITUTE OF BUSINESS ADMINISTRATION (IBA) KARACHI			
BILLS OF QUANTITIES			
PROJECT NAME: SLIDING WHITE BOARD AT CLASS ROOM CFC-5 FAISAL BUILDING			
LOCATION: IBA CITY CAMPUS KARACHI			
BUILDING NAME: FAISAL ACADEMIC BLOCK			
Ref.	DESCRIPTION	Quantity	Unit
1.0	DISMANTLING EXISTING WHITE BOARD & WOODEN WALL Carefully dismantle and remove the existing whiteboards (02 Nos.), including wooden wall paneling and framing. The scope of work shall include removal of the whiteboards, handling, shifting, and storage at locations as directed by the Representative, cleaning of the work area, and disposal of all debris and waste materials from the site. The work shall be completed in all respects.	1	Job
2.0	NEW WALL & FIXED WHITE BOARDS Installation of the existing 02 Nos. fixed white boards (4'-0" x 8'-0"), including the supply and installation of complete Partial wood framing and 10 mm MDF wall cladding with approved paint finish. The scope of work shall also include provision of the required space and additional support for the 2 LED screens displayed at the center of the wall. The Contractor's scope shall include all materials, fittings, accessories, and labor required for complete installation, complete in all respects & site requirements. Wall Size: 32' x 10'	1	Job
3.0	SLIDING WHITE BOARDS Install 02 Nos. sliding whiteboards measuring 4'-0" x 8'-0" each, complete with an aluminum sliding frame fabricated from aluminum sections of ALCOP, Prime, or Equivalent, with a minimum thickness of 1.2mm. The work shall include a complete sliding mechanism that matches the existing IBA specifications, including imported track wheels, rail channels, rollers, hangers, accessories, hardware, fasteners, fittings, and all necessary fixing materials to ensure smooth, durable operation.	1	Job