

Institute of Business Administration (IBA)

Main Campus

BOQ of Wooden Partition & Mobile Drawer in MARCOM OFFICE

RENOVATION WORK AT FAUJI BUILDING

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>LOW HEIGHT Partition with MDF Table Top</u> Providing and fixing in position 4'-0" HT. Wooden Partition work along with 16 mm thick Table top as per drawing using partial wood frame work of 1.5 inch (thick) and 2 inch wide (24" horizontally and 18" vertically) with 16 mm MDF laminated sheets of ZRK brand or Equivalent on both sides finished of approved shade and colour as shown in drawings.The sides & bottom of table top shall be covered by Partial wood frame to support. Provide 4" wide Aluminium skirting at the bottom of partition on both side.All exposed wood surfaces to be finished with wood lacquer polish and necessary beeding (3mm thick Partial Wood) of approved shades as directed including all necessary fittings/hardware and wood preservative (Termite Proofing) etc. as per list of approved material and as approved by the Engineer Incharge complete in all respects.</p>	128.0	Sft.
2	<p><u>Removal of Existing Wooden Cabinets & Shelves</u> Removal of existing shelf & cabinets in a usable condition and handed over the material to client in good condition, complete in all respect as directed by Engineer Incharge.</p>	162.0	Sft.
3	<p><u>Removal & Refixing of Dry Wall & Glazed Partition with Door</u> Removal & Refixing of Dry Wall partition & Glazed Partition with Door on designated place including repairing of damages area with new partition, painting, fixing etc complete in all respect.</p> <p>NOTE: -As per attached BOQ. -Site Visit is mandatory before submission of quotation. -SST 13% will charge</p>	103.5	Sft