

6. Bill of Quantity

CLEANING & PAINTING PROCESS TANK OF STP
(ONE JOB)

S #	Description	Unit	Rate	Total Amount
1	<p>STP-Process Tank Cleaning and Painting Work including the following:</p> <ul style="list-style-type: none"> Septic Tank Plant Cleaning through Sucker Bowser – STP Painting, Collection, Transportation & disposal at IBA main campus. STP Septic Tank Sizes in feet <ol style="list-style-type: none"> RCC Slab for Sewerage Treatment plant. Size: 28 X 11 X 11 FT = 3340 Sq ft UG holding Tank # 2 Size: 12 X 35 X 16 FT = 6720 Sq ft Unnamed Tank Size: 5 X 5 X 16 FT = 400 Sq ft US Storage Irrigation Tank # 1 Size: 17.5 X 20 X 12 FT = 4200 Sq ft <ul style="list-style-type: none"> Waste Disposal Procedure/Techniques <p>STP waters from designated 4 Tanks will be removed through Bowser along with sludge- Waste water shall be disposed to designated plant/area in Karachi.</p> <ol style="list-style-type: none"> STP 1 - Shall be cleaned inside & painting after removal of water/sludge STP II, iii & iv - Waste water shall be removed Manpower/Machineries from Contractor <ul style="list-style-type: none"> Rates inclusive of Labor & transportation <ol style="list-style-type: none"> Sucker bowser STP Grinding and Epoxy paints (Applying 1-coat of High Built Zinc Rich Epoxy Primer. Thickness 200 microns) Applying 2 coats of coal tar Epoxy C-200. Thickness 400 microns Proper disposal of sewerage water and sludge from holding tank during the cleaning of process tank <p>Cost of all the prerequisite material and activities to complete the job must be included in the price.</p>	1 Job		
Total Amount – PKR			7,88,000.-	7,88,000.-
SST				
Grand Total Amount Including All Tax – PKR				7,88,000.-

Syed Akbar Hussain Kazmi
Member - PC
Manager Finance (Payable)
IBA Karachi

JR. SHAHID MIR
Chairman - PC
Assistant Professor - Management
IBA Karachi

M. HARI S QURESHI
External Member - PC
Procurement Specialist
University of Karachi

Stamp & Signature
Stamp: GE
Handwritten signature