

Institute of Business Administration (IBA)

Main Campus

BOQ of Wooden Partition & Mobile Drawer in ADMIN DEPARTMENT OFFICE RENOVATION WORK AT FAUJI BUILDING

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>LOW HEIGHT Partition with MDF Table Top</u> Providing and fixing in position 4'-0" HT. Wooden Partition work along with 16 mm thick Table top as per drawing using partial wood frame work of 1.5 inch (thick) and 2 inch wide (24" horizontally and 18" vertically) with 16 mm MDF laminated sheets of ZRK brand or Equivalent on both sides finished of approved shade and colour as shown in drawings.The sides & bottom of table top shall be covered by Partial wood frame to support. Provide 4" wide Aluminium skirting at the bottom of partition on both side.All exposed wood surfaces to be finished with wood lacquer polish and necessary beeding (3mm thick Partial Wood) of approved shades as directed including all necessary fittings/hardware and wood preservative (Termite Proofing) etc. as per list of approved material and as approved by the Engineer Incharge complete in all respects.</p>	169.3	Sft.
2	<p><u>Mobile Drawer (1'-8"x 1'-6"x2'-5")</u> Cabinet Specification: • Made up of 20 mm ($\frac{3}{4}$") thick Dull White MDF laminated Sheet of ZRK Brand or Equivalent on top, sides, bottom, shelves, and shutters • 6 mm thick marine ply at the back • Box-type hinges of approved make • PVC Lipping finished with melamine of approved laminate on all the shutter edges. • External surfaces finished with 1 mm thick Laminate of approved make • 20 mm thick Dull White MDF laminated shelves, width & depth shall be as per drawing (approx./divided equally) • Complete with all necessary approved fittings hinges, locks of KHAS or Equivalent, 150 mm long SS brush-finished handles, tower bolts, etc.</p> <p>• Providing of Wheels below drawer.</p>	4.0	Each

Institute of Business Administration (IBA)

Main Campus

BOQ of Wooden Partition & Mobile Drawer in ADMIN DEPARTMENT OFFICE RENOVATION WORK AT FAUJI BUILDING

1. Item No.	2. Description of Item	3. Quantity	4. Unit
3	<p><u>Wall Mount Cupboard</u> Cabinet Specification: • Made up of 20 mm ($\frac{3}{4}$") thick Dull White MDF laminated Sheet of ZRK Brand or Equivalent on top, sides, bottom, shelves,shutters and drawer along with 1.5" thick x2.5" wide partial wood frame . • 6 mm thick marine ply at the back. • Box-type hinges of approved make. • PVC Lipping finished with melamine of approved laminate on all the shutter edges. • External surfaces finished with 1mm thick Laminate of approved make • 20 mm thick Dull White MDF laminated shelves, width & depth shall be as per drawing (approx./divided equally) • Complete with all necessary approved fittings hinges, locks of KHAS or Equivalent, 150 mm long SS brush-finished handles, tower bolts, etc.</p>	47.5	Sft
4	<p><u>Dismantling of Block Work.</u> Dismantling of existing block masonry walls, partitions, parapets etc, at any level manually or mechanical using breaker, handing over of reusable material like doors, glass, aluminium frame etc and disposed off rubbish material from site as per direction of the Engineer.</p>	115.5	Sft
5	<p><u>Cement Plastering & Tile Repairing Work</u> Supply, make, apply and cure, cement sand plaster as specified including fixing of dismantled/ removed tiles with bond, filling with grout , corners, edges complete in all respect as per direction of Engineer Incharge.</p> <p>Note: -Site Visit is mandatory before submission of quotation. -SST 13% will charge</p>	1.0	Job