

6. Bill of Quantity / Scope of Work

Water Boring Works with Commissioning

S. #	Item Details	Qty	Unit Rate	Amount (Rs.)
	<u>Drilling</u>			
1	12" dia drilling in all types of Strata including Drilling shall be carried out via electrically operated Boring Machine			
	Bore Depth: 400 feet			
2	Mild Steel Pipe , Cement , Sand			
	with Installation with fitting For Base toping			
3	<u>CASING</u>	02		
	Size: 8"			
	Material : UPVC			
	Class : C			
	Brand : Total /Prince or equivalent			
4	<u>GRAVEL</u>			
	Marble Chips			
	As per required quantity			
	<u>ACCESSORIES</u>			
5	2 "HD. Polyethylene 100 (P.E) Pipe- In feet			
6	Stainless steel shilling wire 6mm -In feet			
7	Electric Flat Cable 6mm 3 core			

725000/ 1450,000



Page 14 of 23

MEMBER
CENTRAL PURCHASE COMMITTEE

CHAIRPERSON
CENTRAL PURCHASE COMMITTEE

MEMBER (EXTERNAL)
CENTRAL PURCHASE COMMITTEE

8	Motor control unit		
9	Dry level controller with cable		
10	Brass Union 2" Fabricated		
11	Installation with cartage		
12	PUMP		
	2 HP Pump (IMPO-TURKEY) or equivalent		
13	Installation with Testing and Commissioning		
Total Amount Inclusive all Taxes			1480000 -

Total Amount Rupees (in words) Fourteen Lacs fifty thousand only

- * Work Completion: 4 to 5 weeks After P.O.
 * Power will be supplied by IBA



2/2



Stamp & Signature

[Signature]
 MEMBER
 CENTRAL PURCHASE COMMITTEE
 INSTITUTE OF BUSINESS ADMINISTRATION
 KARACHI

CHAIRPERSON
 CENTRAL PURCHASE COMMITTEE
 INSTITUTE OF BUSINESS ADMINISTRATION
 KARACHI

Page 15 of 23

MEMBER (EXTERNAL)

