

BOQ-**Repairing of P.E Pipe line outside IBA Main Gate No 1**

S.N	Specifications	Required Quantity	Unit	length (ft)	Width (ft)	Depth(ft)	Total
1	Road Cutting of Main Water Supply Line	75	cft	120	2	5	1200
2	Repairing of 6" HDPE Pipe for water Supply line using fusion connection with Main water Supply line including connection all complete	1	Lumpsum	120			
3	Repairing of sand bed under pipe line and sides of pipe through out the length	10	cft	120	1	0.5	60
4	Back Filling	2	cft	120	2	4	960
4	Provide and Laying of Asphalt Base coarse 3" thick layer	2	cft	120	2	0.25	60