

INSTITUTE OF BUSINESS ADMINITRATIC

PROJECT: Renovation of Toilet at Fauji Foundation Buildi

1.	2.
S. No.	Description
1)	Dismantling Work
	Dismantling / cutting / removal of existing block masonry, tiles on floor & walls, plaster on walls & floor including wall chipping & removal of debris outside premises and handing over re-usable material like Camode, flush tank, Wash Basin etc. to Engineer Incharge, complete in all respect as per site requirements.
2)	Cement Board Partition
	Providing & fixing 100 mm thk Cement board partition of Envicrete Brand - constructed using Aluminium metal stud as framework @ 610mm c/c and fixed with two layers of 12.5mm tapered edge Cement board Sheet on either side of the aluminium Framework, uisng dry wall screws, jointed and finished with requisite filler, paper tape, finisher and primer suitable for Cement boards. Partition to have glass wool insulation of density 48 kg/cum wrapped neatly in bags as per approval. The outer skin shall be finished with 2/3 coats of acrylic emulsion paint with approved primer, all as per approval. All components to be of Envicrete Brand.

INSTITUTE OF BUSINESS ADMINITRATIC

PROJECT: Renovation of Toilet at Fauji Foundation Buildi

1.	2.
S. No.	Description
4)	Providing & Fixing of Porcelain Tiles in Washroom
	Porcelain Tiles.
	Supply and lay full body porcelain tiles of Shabbir Brand (Prime Quality) or approved equivalent as per approved sample, sizes (12" x 24") or as desired and colors, set with cement slurry including filling and grouting the joints with matching pigments & bond upto 7 ft. height,complete in all respect as per drawing and as directed by the Engineer.
a)	On Floor:- With 40mm (2 inch.) thick setting bed in (1:6) mortar.
b)	On Dado (7ft. High) :- with 20mm thick rough plaster in (1:6).
5)	Plumbing Piping.
	Facility Water Distribution PPR Pipes.
	Supply and lay PPR pipes of Dadex - Ethernet or equivalent for hot and cold water distribution at any height system including specials such as tees, bends, elbows, unions, plugs, reducers etc. with heat fusion jointing method including cutting holes in masonry or concrete in wall, floor and slab and chiseling wall and floor and making good the same, complete in all respect as per drawing, specification and as directed by the Engineer. Nominal internal diameter shall be as follows:-
a)	20mm (3/4") Dia
	Note: This item includes removal of existing pipe lines

INSTITUTE OF BUSINESS ADMINITRATIC**PROJECT: Renovation of Toilet at Fauji Foundation Buildi**

1.	2.
S. No.	Description
6)	Facility Sanitary Sewerage.
	Nikasi Pipes.
	Supply and lay UPVC pipes of Pak Arab/ Steelex (SDR-41) or equivalent, Nikasi for soil, waste and vent system including specials such as P-Trap, tees, bends, plugs, reducers, etc. with solvent cement jointing / rubber ring push fit jointing method including cutting holes in masonry or concrete in walls, floor and in slab, making good the same, complete in all respect as per drawing, specification and as directed by the Engineer.
a)	110 mm (4" Dia) diameter.
	Note: This item includes removal of existing pipe lines
7)	Supply and fix one piece commode of approved quality.
	Supply and fix one piece toilet Commode of Porta or equivalent , in white or coloured with "P or S" trap of vitreous china, size shall be 741 x 438 x 637 mm with symphonic flushing mechanism 1.0 No. and seat cover with hydraulic including all internal fittings with connection pipes, Tee stop cock etc. of master (Code: 076-CP) complete in all respect as per drawing and specifications.
8)	Supply, fix muslim shower complete with PVC flexible pipe,Double Bi
	Supply and fix muslim shower complete with PVC flexible pipe (size:12mm dia), and double Bib Cock of matching knobs, of Master (Code:2015,078-CP) or equivalent, 1.0 No. complete in all respect as per drawing and as directed by the Engineer.

INSTITUTE OF BUSINESS ADMINITRATIC

PROJECT: Renovation of Toilet at Fauji Foundation Buildi

1.	2.
S. No.	Description
9)	Providing and fixing Stainless Steel Floor Trap
	Supply and fix in position Stainless Steel Floor Trap with top tile & strainer of local approved - Nikasi or equivalent, floor trap shall be connected to a waste stack with bend, complete in all respect as per specification.
10)	Bathroom Accessories.
	Supply and fix following bathroom accessories in chrome plated of Master or equivalent approved, complete in all respect as per specification.
a)	Toilet Paper Holder
11)	Wooden Panel Door
	Providing,fabricating & fixing in position in given sizes, semi solid block board door shutter 1- 1/2" thick including 1/8" thick commercial ply on both sides, including 1/2" thick Partal wood lipping all around, shutter to be fixed with Aluminium frame 4" wide & 1.2 mm thick & hardware of approved quality/make such as hinges, bolts,handle, door lock etc .Complete in all repect as per specification and as directed by the Engineer Incharge.

NOTE:

-As per attached BOQ.

-Site Visit is mandatory before submission of quotation.

-SST 13% will charge

ON, KARACHI

ng, IBA Main Campus

3. Qty.	4. Unit
1	Job
50	SFT

ON, KARACHI

ng, IBA Main Campus

3. Qty.	4. Unit
15	SFT
95	SFT
1	Job

ON, KARACHI

ng, IBA Main Campus

3. Qty.	4. Unit
1	Job
1	No.
b Cock	
1	No.

ON, KARACHI

ng, IBA Main Campus

3.	4.
Qty.	Unit
1	No.
1	No.
2	Nos.