

SCOPE OF WORK

S.No.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Dismantling the existing fixed M.S. sheet by cutting, with due care including folding, planks grinder disc ect and protection the glass and aluminum frame existing their, all tools plants cost included into the rate all MS sheet would be handed over to IBA. Complete the job in all respect.	SFT	264		
2	Providing and fixing in position 2"x2"x2"" thick angle Iron frame plus 2"x2" x 2"" thick flat strip at mid points of the frame welded with existing MS Columns at both edges , all tools plants folding welding machine rods, folding and planks everything included. after fixing red oxide paints would be made over newly fixed frame 2" x 2" x 2"" thick flat strip	sft	264		
3	providing and fixing Expanded Metal/MS Jali 1/2" jali, welded it all maround with angle iron frame ,all tools , plants welding's folding and planks also including into it complete in all respect and as per Engineer.	sft	264		

4	providing and fixing 1/2" thick ply at the back of framing which would used as a shuttering joint with frame with ply by cut screws. All tools plants , folding and planks also included , Complete in all respect as per the instruction of Engineer	sft	264		
5	Providing and Fixing 1:2:4 concrete using 0 to 5 no. crush chips about 1.5" thick concrete would be placed, all tools , plants folding curing etc would include in this item rate, complete in all respect as instruction of Engineer.	sft	264		
6	Providing and Placing 1:4 plaster 1" thick over the newly placed concrete using SBR in niro to joint old and new concrete, all tools plants folding curing etc. included into it.	sft	264		
7	Providing and laying 03 coat of weather shield paints as existing colour and texture al tools plants will be included	sft	396		
Total					
13% SST					
Total Amount					