

INSTITUTE OF BUSINESS ADMINISTRATION (IBA) KARACHI								
IBA HOSTEL MAIN CAMPUS KARACHI.								
BILL OF QUANTITIES FOR SUPPLY, FABRICATION & ERECTION OF STAIR CASE & CORRIDOR HAND RAILING AT IBA HOSTEL								
S. No.	Description	Qty	Unit	Material Rate Rs.	Material Cost Rs. (3x5)	Installation Rate Rs.	Installation Cost Rs. (3x7)	Total Amount Rs. (6+8)
1	2	3	4	5	6	7	8	9
A	STAIR CASE HAND RAIL Supply,Fabrication, & Erection in position at site of Stair Case & Corridor hand rails Complete as per existing and as per specification. The railing comprises of 3"x1" Rectangular Pipe 16 SWG rectangular tube 16 SWG thickness with intermediate pipe support of 1"x1" rectangular pipe including grinding , painting with Enamel Paint in approved shade and colour and transportation, loading, unloading fixing in position complete as per direction complete as per direction complete in all respects.	485	RFT	0	0	0	0	0
	Sub-Total Carried to Summary							0
	Sub-Total Carried to Summary							