

# Institute of Business Administration (IBA)

## Main Campus

Project: IBA, Main Campus

### Works:MS Pole 8" Dia Erection

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><b><u>MS POLE (8" DIA) ERECTION WORK</u></b></p> <p>Erection &amp; fixing of client provided MS Pole (8" Dia) pole by providing &amp; welding of 20" x 20" x 0.5" thick ) MS Base plate along with 4 vertical gussets of 8" height in required position along with welding and application of two coats of Red Oxide, three coats of epoxy paint on surface complete in all respect as directed by Engineer. The rates includes all labour for cutting, fixing, bending , welding etc.</p> <p>The pole shall be erected and fixed on a 4 No's MS J Bolts of 20 mm dia &amp; upto 2.5' length and 20"x20"x0.5 thick MS Base plate. The J bolts &amp; MS Base Plate shall be welded along with Concrete foundaion reinforcement. The steel reinforcement shall consist of 16 mm dia bars @ 6" C/c both direction in a double cage form. The concretefoundation shall be 1:2:4 ratio and size (2.5'x2.5'x2' ) complete in all respect.</p> <p><b>NOTE:</b> <b>-Site Visit is mandatory before submission of quotation.</b> <b>-SST 13% will charge</b></p>	1	No.s