

Institute of Business Administration (IBA)

Main Campus

Project : House No. C-16 (Staff Town)

Works : Repair & Maintenance Works

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>Wood, Plastics and Composites - 06</u> <u>Kitchen Cabinets.</u> Supply and fixing cabinets according to the size and dimensions as per site condition , made with 16mm thick Super Gloss MDF Lmainated Sheet of ZRK Brand or Equivalent, 2" x1" thick partal wood frame and 1mm thick PVC lipping of approved colors including horizontal or vertical partition in inside, drawers & channel with handles of KHAS or Equivalent , fixing cabinets to wall with expansion bolts of 10 mm diameter at 600 c/c and all relevant hardware i.e. piano hinges, locking arrangement, handles, painting and polishing etc complete in all respect as shown on drawing specification and as directed by the Engineer. (Note: Sample to be approved by Client prior to start of work.)</p>		
a	Wall Hung Cabinet.	45.0	Sft
b	Base Cabinets	25.0	Sft
	Note: This item includes the removal of existing cabinets.		
2	<p><u>Dismantling of Kitchen Counter Top with Concrete Slab</u> Dismantling of existing reinforced concrete kitchen slab, kitchen counter top etc, at any level with bare or plastered surface manually or mechanical using breaker etc, with sorting out demolished material and stacking of serviceable material such as re-useable steel in safe custody till it is handed over to the owner and disposal of un-serviceable material as per specification and as directed by the Engineer.</p>	30.0	Sft
3	<p><u>Concrete Block Masonry</u> Supply and lay, in (1:3:6) machine made solid block masonry straight or curve, as specified, set in cement - sand mortar with raking out joints on both sides, at any level and where masonry abuts columns, including curing etc complete in all respect as per drawings and specification.</p>		
	<u>Below / Above plinth , set in (1:4) mortar.</u>		
a	100 mm thick	25.0	Sft

Institute of Business Administration (IBA)

Main Campus

Project : House No. C-16 (Staff Town)

Works : Repair & Maintenance Works

1. Item No.	2. Description of Item	3. Quantity	4. Unit
4	<p><u>Kitchen Counter Top.</u> Supply and lay 20mm thick, chemical polished marble slab as specified of approved sample over a setting bed of 40mm thick cement - sand mortar setting bed in (1:4). This includes the cost of filling and grouting the joints with white cement and matching pigment complete in all respect as per drawing, specifications and as directed by the Engineer.</p>		
a	<p><u>Plain Verona (Spot Free)</u> For kitchen / Vanity Top with bull nosing of half round, including making of openings for sink / wash basin with molding around the openings.</p>	25.0	Sft
5	<p><u>Cement Plastering</u> Supply, make, apply and cure, cement sand plaster as specified including jambs, junctions, corners, edges and round surfaces etc, complete in all respect as per drawing and specifications.</p>		
a	<p><u>20 mm thick in (1:4) mortar.</u> To interior / exterior surfaces.</p>	60.0	Sft
6	<p><u>Concrete Counter Slab (1:2:4)</u> Supply and place in position concrete Counter Slab upto 3" thick with necessary reinforcement of 8 mm dia bars @ 250 mm c/c both ways as per detailed drawing with complete in all respect, specification and as directed by the Engineer.</p>	25.0	Sft
6	<p><u>Metal Exhaust Fan 12" Dia</u> Supply and place in position 12" Dia Metal exhaust square fan 1350 RPM & 40 Watts including cutting of wall & fixing in position of GFC, Royal Brand or approved equivalent complete in all respect.</p>	1.0	Each
	<p>NOTE: -As per attached BOQ. -Site Visit is mandatory before submission of quotation. -SST 13% will charge</p>		