

BOQ FOR SINAGE BOARD WALLS IBA KARACHI

S.No.	Specification	Quantity	Unit	Rate	Amount
1	EXCAVATION				
	Excavation in foundation at any soil/ stratra including levelling , dressing and compaction & back filling plus disposals of extra soil beyong the IBA limits complete in all respect.	180	cft		
2	LEAN 1:4:8				
	Providing and laying lean (1:4:8) concrete in SR Cement 6" thick including compaction , levelling and curing etc. complete in all respect as per instruction of Engineer.	36	cft		
3	BLOCK MASONARY				
	Providing and laying cement concreting solid block 1:3:6 ratio including mortar, racking out joints and curing etc. completed in all respect as per instruction of Engineer.				
i	6" thick [Planter Walls]	27	sft		
ii	8" thick [Main wall]	102	sft		
iii	12" thick [Below ground level foundation]	38	sft		
4	Rough Plaster				
	Providing and laying 1:4 rasion 3/4"thick cement concrete plaster both sides including all tools and plants plus curing as per instruction of Engineer.	251	sft		
5	TERRACOTTA CLADING				
5.i	providing and laying 3/8" thick of Sill batta (terracotta) prepolished as per existing sizes with cutting fixing in place and cement sand mortar ratio 1:4 , complete in all respect.	241	sft		
5.ii	Providing and Laying terracotta coping at top of wall and planter as per existing ,both side edge making (gola making both sides) 1" thick & 10" wide pre polished complete in all respect as per instruction of Engineer.	32	rft		