

S.No	Item Description	Qty	Unit	Price
1	Dismantling of Cables, Connections and Breaker (Battery Room to UPS and UPS to Main DB Box).	1	Job	
2	Supply and Installation of Breaker Box with Indication Lights 03 No and Breakers 63A 3 Pole 02 No.	1	Job	
3	Supply and Laying of Cable 16mm 4C +10mm 1C Earth With Lugs and Connections (UPS to New Breaker Box).	Running Feet	As per Actual	
4	Supply and Laying of Cable 25mm 1C x 2 Cable with Connections (Battery Room to UPS Room)	Running Feet	As per Actual	
5	Supply and Installation of 3 Pole 80 Amps (Magnetic Trip 1600 Amps).	1	Job	