

**Comparative Statement**

**Supply, Installation, Testing and Commissioning of 400 KVA (± 5%) Standby Diesel Generator set at Boys Hostel IBA Main Campus Karachi**

**Tender # ME/11/22-23**

S. #	Items	Qty	Unit	M/s. Greaves Pakistan (Pvt) Ltd		M/s. S. M. Jaffer & Co		M/s. Allied Engineering & Services (Pvt) Ltd		M/s. K A N Engineering & Services		M/s. Cemcon		M/s. Build Con		
				Rate	Amount	Generator Rating	Corrected Amount	Generator Rating	Amount	Generator Rating	Amount	Generator Rating	Amount	Generator Rating	Amount	Generator Rating
1	Supply ,Installation, Testing & Commissioning of brand new Diesel Generator set of at least 400 KVA ( ±5%) STAND BY rating, 415V, 50 Hz, 3 Phase, 4 Wires, 1500 RPM, 0.8 pf suitable for operation at 50 degree Celsius and 90% relative humidity, with Main Circuit Breaker as per load/capacity with Sound attenuated /weather proof canopy, Electronic Governor Diesel Generator set as per specifications of bidding documents, complete in all respect as per ISO standards. Engine manufactured by Cummins, Perkins, Caterpillar or Equivalent. The rate is inclusive of all cost of loading, unloading transportation cost and all local, federal or provincial taxes.	1	Nos	Rs. 25,157,600.00	Rs. 25,157,600.00											
2	Supply, Installation, testing & commissioning of 2x120 Sq mm 4 Core Cu/PVC/PVC 600/1000 V Power Cable from Generator to ATS panel and configuration for automatic start during utility supply failure condition, complete in all respect non armored laid in UPVC Pipe sleeve cable manufactured by Pakistan Cable, Fast Cable, Newage, Pioneer or equivalent	100	RFT	Rs. 22,000.00	Rs. 2,200,000.00											
3	Supply, laying, installation, testing and termination of 95 sq.mm single core copper PVC insulated earth cable for neutral and body grounding connections as per specification. Manufactured by Pakistan cable, Fast Cable, Newage, pioneer or equivalent.	100	RFT	Rs. 1,423.00	Rs. 142,300.00											
4	Supply, laying, testing, commissioning, and termination of 2.5 sq.mm 3 core Cu/PVC/PVC insulated Control cable as per specification. Manufactured by Pakistan cable, Fast Cable, Newage, pioneer or equivalent	300	RFT	Rs. 325.00	Rs. 97,500.00											
5	Supply, installation & testing of earthing set comprising of Bore earthing up to 100 RFT depth or water-level, lime, salt & charcoal mixture, packed hard including excavation & perfect back filling. 50 mm dia uPVC pipe and copper wires up to test terminal and also providing, fixing & connection of 300mm x 50mm x 5mm Earth test terminal with brass nuts bolts & washer along with construction of RCC inspection chamber with heavy duty CI cover Lid and lock protection complete in all respect as directed by engineer in charge. The Contractor shall perform earthing resistance tests after installation of earth pits and add necessary items charcoal, salt etc. until the optimal level of earth resistance (less than 4 ohms) is achieved as per applicable standards.															
5a	earthing pit of body of Generators	1	Job	Rs. 444,860.00	Rs. 444,860.00											
5b	earthing pit of neutral of Generator	1	Job	Rs. 444,860.00	Rs. 444,860.00											
<b>Total Amount without Tax</b>					Rs. 24,141,627.12											
<b>Total Amount with Tax</b>					18% GST		Rs. 28,487,120.00									

Non Responsive: did not meet the eligibility criteria

**M.HARIS QURESHI**  
External Member - PC  
Procurement Specialist - HEJ  
University of Karachi

**DR. SHAHID MIR**  
Chairman - PC  
Assistant Professor - Management  
IBA Karachi

**Syed Akbar Hussain Kazmi**  
Member - PC  
Manager Finance (Payable)  
IBA Karachi

**SYED WAJEEH ZAIDI**  
Member - PC  
Sr. Manager IT  
IBA Karachi

**EXTERNAL MEMBER**  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI