

Institute of Business Administration (IBA)

Main Campus

Project :HR Meeting room, IBA Main Campus

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<u>Resizing of the Existing Wooden Partition</u> Resizing the existing wooden partition by cutting, trimming, planing, sanding, and repairing edges as per drawing, including all labor, tools, and finishing works, complete as per instructions of the Engineer.	1.0	Job
2	<u>Fixed Glazing with Wooden Frame with Polish Finish.</u> Provide and install in position fixed glazing with wooden frame, consisting of 8mm thick Tempered clear float glass of Tariq/Ghani or Equivalent, fixed with 2" x 4" Solid Oak wood frame (guaged wood) as per Drawing Polish finished on wooden frame including all required material , hardware , rubber & neoprene gasket of approved quality, silicone sealant, acoustic Tape on joints, fixing arrangements, wastage, lifting, cutting, etc., complete in all respect. Wooden Support should be provided from celing.	76.7	sft
3	<u>Sliding Wooden Door</u> Providing, fabricating, and installing a complete sliding door assembly comprising a solid wooden frame of 2" x 4" of Oak Wood. The frame shall include all required grooves and rebates to receive the sliding door panel. The door panel shall consist of a wooden perimeter stile/rail section with an inserted clear 8mm tempered glass panel, fixed securely with wooden beading and silicone sealant. Work shall include supply and installation of all necessary sliding channels, rollers, guides, stoppers, stainless-steel screws, brackets, cutting, edge finishing, polishing/paint, hardware fitting, alignment, and smooth operation testing, complete in all respects as per drawing and instructions of the Engineer.	23.5	sft