

## SCHEDULE – A TO BID


**SCOPE OF WORK****Laying 2" Dia Domestic Connection from KWSB Line to IBA Staff Town**

IMPORTANT: The bidder should include in his rate quoted all the expenses incurred for obtaining "Right of Way permission from Concern department" and sanction of Connection line charges. IBA shall pay only the Challan amount issued by KWSB and contractor will bear all the expenses otherwise in this regard.

S.NO	ITEMS OF WORK	UNIT	QUANTITY	RATE	AMOUNT
1	Excavation for water supply lines in trenches, and pit in any type of soils clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of tranches to correct level and grade, cutting joint. Holes and disposal of surplus earth within a one chain as directed by Engineer in charge Providing fence guards, lights wherever required lift up to 10 to 12ft (3 to 4 m).	Cft	8000	40	= 320,000/-
2	Providing & fixing M.S flange made of M.S plate, having a thickness and total weight as mentioned against each item it includes the cost of making holes, facing, welding, nuts, bolts, rubber pacing, white lead, fitter, cartage etc. complete 2" Weight (2.020). The material shall be approved and as per standard of KWSB.	Nos	11	10,000	110,000/-
3	Providing laying & , finishing in trenches including lifting, jointing & testing etc. complete In all respect, the high density polyethylene P.E pipe (HDPE-100) conforming to ISO 4427/BIN8074/8075-BS3580 & PSI-3051 PN-12N (2" dia). This rate also include all the testing & commissioning as per KWSB.	Rft	200	400	80,000/-
4	Providing & fixing of Kitz Company (JAPAN) or equivalent Gates valve S.S heavy pattern (Test pressure 21.0 kg/Sq.cm or 300 lb/sq.inch) 2" dia	Nos	3	150,000	450,000/-
6	Providing & fixing of Kitz Company (JAPAN) or equivalent Check valve S.S heavy pattern (Test pressure 21.0 kg/Sq.cm or 300 lb/sq.inch) 2" dia	Nos	2	140,000	280,000/-
7	Providing & fixing of Kitz Company or equivalent 2" dia strainer brass	Nos	1	160,000	160,000/-



8	Construction of R.C.C Chamber cover and frame 6" thick R.C.C walls set in 1:6 C.M 6" thick C.C. 1:4:8 in foundation, 2" thick C.C. 1:2:4 flooring ½" thick cement plaster 1:6 to all inside wall surfaces, top and bottom outer side RCC wall surface 6" deep up to roof RCC i/c. M.S. foot rest 5/8" dia bars every 2'-0" deep, curing, excavation, dewatering, re-filling, etc. complete 10 X 6 X 10 (Inside Dimensions) and roof 10 X 6	Nos	1	27,00,000	27,00,000/2
9	Providing & fixing of Water Meter Kitz Company or equivalent 2" dia fixing nuts, bolts, rubber sheets	Nos	1	80,000	80,000/2
10	Providing & fixing M.S Spilt Collar and TEE on PRCC Pipe of different sizes having wide as mentioned against each items, to suit the size of connection, fabricated with ½ thick M.S plate excluding the cost of neck its including's the cost of 1" thick M.S flange, either a total weight as mentioned against each items it also includes the cost nuts & bolts, rubber packing, labor and sealing material and all the tools and plants, etc. complete. 33" X 33" (Weight 338.390) 3'-6"	Nos	1	240,000	240,000/2
11	Providing & fixing of 0-9" long - 3/8" thick M.S Neck to existing M.S pipe or to a split collar tee having a total weight as mentioned against each item. It includes the cost of fabrication and welding to the split collar tee. 2" Weight (4.773)	Nos	1	10,000	10,000/2
12-	Dewatering Expense (including Petrol Labors and		4	30,000	120,000/2
13-			8000	10	80,000/2
14	Refilling the excavated in trenches 10" X 200 thick Layer i.c watering ramming to full compacting etc complete (Provisional Quantity	Sqft	8000	10	80,000/2



TOTAL AMOUNT	= 4,710,000/-
ADD 15 % SRB	= 706,500/-
GRAND TOTAL AMOUNT	= 5,416,500/-
Submission of work completion certificate & as Built drawing of the work from KU that the Contractor has made good all the damages /back filled the excavated area and had restored in its original condition. Earnest money shall only be released upon submission of such certificate.	

Grand Total Amount in Words:

Rupees: FIFTY FOUR LAC SIXTEEN THOUSAND FIVE  
HUNDRED ONLY



Stamp & Signature