

6. Bill of Quantity**SCOPE OF WORK****Waterproofing Works in Aman CED and VFR Buildings**

| S # | DESCRIPTION | QUANTITY | UNIT | RATE | AMOUNT |
|-----|--|----------|------|------|---------|
| 1 | Cleaning of Roof & Filling of Cracks in Roof Screed Cleaning of Roof including repairing of cracks in existing roof screed wherever required by using FOS Pak Primer putty /Concrete Crack filling treatment as per manufacturers direction & recommendation complete and disposal of the debris at designated place out side the IBA premises as directed by Engineer Incharge. | 10,000 | Sft | 5 | 50000 |
| 2 | Roof Treatment By EXPAN BRUSH RFX BY FOSPAK or Equivalent (equivalency should be approved by IBA) Providing & applying Elastomeric cementitious waterproofing coating Expanbrush Rubberflex RFX manufactured by FOSPAK or equivalent as approved in two coats the total dry film thickness should not be less than 1.5mm . The material is to be applied as per application procedure prescribed by the manufacturer by qualified / specialized applicator. Application: EXPANBRUSH RFX*acrylic polmer modified cementious water proof coating should be applied by brush, roller, trowel or spray in two coats application on horizontal surfaces at a minimum wet film thickness of 1.0 mm as first coat and 1.5mm thickness of the second coat the minimum dry film thickness should not be less than 1.5mm Spalled and deeply disintegrated concrete should be removed to sound concrete and repaired with a Expanchem Fospak repair system This rate is inclusive of all type of labour, material, tools & plants, Scaffolding , lifting, testing of surface by ponding of water using sand or as per prescribed etc. | 26,137 | Sft | 66 | 1725042 |

M. HANIS QURESHI
External Member - PC
Procurement Specialist - HEJ
University of Karachi

DR. SHAHID MIR
Chairman - PC
Assistant Professor - Management
IBA Karachi

Syed Akbar Hussain Kazmi
Member - PC
Manager Finance (Payable)
IBA Karachi

Al Inaya Enterprise
Proprietor
Stamp & Signature



| | | | | | |
|-----------------------------|---|------|------|-----|-----------------------|
| 3 | Making of 6" x 6" P.C.C Chamfer Providing & making ,Cutting of Old Chamfer , making rough chamfer 6" x 6" in triangular at wall and roof junctions or openings all along the sides of the building and making Chamfer 6" x 6" using concrete ratio 1: 2 :4 having (10 mm) down crush including using of S.B.R with proper binding, curing etc complete in all respect as directed by Engineer Incharge. | 1942 | Rft | 62 | 120404 |
| 4 | Making of 6" x 6" P.C.C Pads (Upto 5" thick) Providing & making ,Cutting of Old Pad , making 6" x 6" in Square shape below PVC, MS Pipes for support and protection all along the building using concrete ratio 1: 2 :4 having (10 mm) down crush including using of S.B.R with proper binding, curing etc complete in all respect as directed by Engineer Incharge. | 400 | Each | 600 | 240000 |
| Total | | | | | = 2135446/- |
| 13% SST | | | | | = 277607.98/- |
| Grand Total with SST | | | | | = 2413053.98/- |

Note:

- The product will be applied by the nominated or authorized applicator and a minimum of 5 years of warranty shall be given by manufacturer. The contractor's performance guarantee shall be released after the completion of two rainy seasons.
- The contractor should calculate the total number of Waterproofing Boxes as per given area and stack the material on site before commencement of waterproofing application.

Grand Total Amount Rupees in Words: Rs. TWENTY FOUR LAC THIRTEEN THOUSAND

FIFTY THREE RUPEES & NINETY EIGHT PAISAS ONLY.

Syed Akbar Hussain Kazmi
Member - PC
Manager Finance (Payable)
IBA Karachi

M. HARIS QURESHI
External Member - PC
Procurement Specialist - HEJ
University of Karachi

DR. SHAHID MIR
Chairman - PC
Assistant Professor - Management
IBA Karachi

Stamp & Signature