

| INSTITUTE OF BUSINESS ADMINISTRATION (IBA) KARACHI | | | | | | | | |
|---|---|-----|------|---------------|---------------|-------------------|-------------------------------------|--------------|
| IBA HOSTEL MAIN CAMPUS KARACHI. | | | | | | | | |
| BILL OF QUANTITIES FOR SUPPLY, FABRICATION & ERECTION OF COMPOUND WALL GRILL AT IBA HOSTEL (BALANCE WORK) | | | | | | | | |
| S. No. | Description | Qty | Unit | Material Rate | Material Cost | Installation Rate | Installation Cost | Total Amount |
| | | | | Rs. | Rs. (3x5) | Rs. | Rs. (3x7) | Rs. (6+8) |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| A | COMPOUND WALL GRILL | | | | | | | |
| 1 | Supply,Fabrication, & Erection in position at site of Compound wall Grill average size 10'-9" x 2'-6" (11 Nos)Complete as per specification. The grill comprises of 2"x1" rectangular tube frame 18SWG thickness with intermediate pipe support of same size and two numbers round pipe 2" dia 18SWG including grinding , painting with Enamel Paint in approved shade and colour and fixing in position complete as per direction. | | | | | | | |
| 1.1 | 11 Nos size av. 10'-9" x 2'-6" | 305 | Sft | | 0 | | 0 | 0 |
| | | | | | | | Sub-Total Carried to Summary | 0 |
| | | | | | | | Sub-Total Carried to Summary | |