

Institute of Business Administration (IBA)

Main Campus

BOQ OF Office Furniture in NTHP Office

RENOVATION WORK AT NBP BUILDING

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>Credenza Cabinet (1'-6" x 1'-6" x 2'-1")</u></p> <p>Cabinet Specification:</p> <ul style="list-style-type: none"> • Made up of 20 mm (¾") thick Dull White MDF laminated Sheet of ZRK Brand or Equivalent on top, sides, bottom, shelves, and shutters • 6 mm thick marine ply at the back • Box-type hinges of approved make • PVC Lipping finished with melamine of approved laminate on all the shutter edges. • External surfaces finished with 1 mm thick Laminate of approved make • 20 mm thick Dull White MDF laminated shelves, width & depth shall be as per drawing (approx./divided equally) • Complete with all necessary approved fittings hinges, locks of KHAS or Equivalent, 150 mm long SS brush-finished handles, tower bolts, etc. 	5.0	Each
2	<p><u>Wall Mount Wooden Cabinet</u></p> <p>Cabinet Specification:</p> <ul style="list-style-type: none"> • Made up of 20 mm (¾") thick Dull White MDF laminated Sheet of ZRK Brand or Equivalent on top, sides, bottom, shelves, and shutters • 6 mm thick marine ply at the back • Box-type hinges of approved make • PVC Lipping finished with melamine of approved laminate on all the shutter edges. • External surfaces finished with 1 mm thick Laminate of approved make • 20 mm thick Dull White MDF laminated shelves, width & depth shall be as per drawing (approx./divided equally) • Complete with all necessary approved fittings hinges, locks of KHAS or Equivalent, 150 mm long SS brush-finished handles, tower bolts, etc. <p>Note:</p> <ul style="list-style-type: none"> -Site visit is mandatory for quotation of rates. -SST 13% will charge. 	80.0	Sft