6. Bill of Quantity

SCOPE OF WORK Painting Works MS Circular Columns & Other Structure at Library

:.#	Specification	Qty	Rate	Amount
1.	Painting Surface Preparation The surface to be over-coated must be dry and free from surface contaminants. Sand down the surface by using sandpaper thoroughly to ensure a smooth finish. Remove all previous paint, dust and residues completely before commencing painting.	6000 sft	10.00	60000.0
	Epoxy Paint Finish Supply and apply one coat of primer and two coats Epoxy paint finish of Berger, ICI or equivalent on MS Columns & other structure by using Brush, Roller or Spray in approved shades, prior to application all surface must be clean, dry, free from all defective, complete in all respect as directed by Engineer and as per manufacturer's recommendations. Berger Epifloor or equivalent should be applied over a suitable primer or build coat. For recoating, the underlying system should be intact, sound and undamaged. Ensure that the surface to be over- coated is clean, dry, free from dust, grease and oil, or any other surface contaminants. Wash surface using fresh water to remove soluble salts. Always ensure to follow the maximum over-coating time for the primer/build coat and it should not be exceeded prior to application. Suitable Primers: Epimastic 3000HS, Epimastic 3100, Epimastic 5100, Luxaprime 1501 Luxaprime 1801 or equivalent	6000 sft	54.0	324000-9
	DR. S.M. FAISAL IRADAT	Don.	38	34,000.09
	2	Member –	PC	
Kter	Cuntal Takal Amanana	ty of Karac	7 7 6	84000.00

University of Karachi

Syed Akbar Hussain Kazmi Member - PC

ager Finance (Payable) IBA Karachi

SYED WAJEEH ZAIDI Member - PC

Sr. Manager IT **IBA Karachi**

Stamp & Signature

Page 14 of 23

It is hereby certified that the terms and conditions have been read, agreed upon and signed.

M/s (alexy Emfort rises
Contact Person: Irfen Alimed
Address A-293 Block- H Navy Novindbool Norcel:
Tel#Fax# Wattsall 2302714527
Mobile # 03 472182472 e-mail: Ivacylety @ gmail. Com

Stamp & Signature