

SCOPE OF WORK

ESTABLISHMENT OF FINANCE LAB AT AMAN CED BUILDING MAIN CAMPUS KARACHI PRICED BILL OF QUANTITY/ ENGINEER'S ESTIMATE

S. No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Providing, laying & Installation of False ceiling using gypsum board with aluminum framing as per design & drawing and specifications complete.	1442	SFT	220/-	317,240/-
2	Providing & installation of Workstation as per drawing & design using ¾" thick 20mm Laminated high density plywood fixed over white soft wood frame complete as per drawing & design and specifications	51	Nos	10,389/-	529,839/-
3	Providing, laying and installation of Electrical Cable, wires, DB board, switches etc complete as per drawing, design complete	1311	SFT	154/-	201,894/-
4	Providing, laying, commissioning Networking (for work station) as per drawing & design and specification	51 nos	Each	1599/-	81,549/-
5	Demolish Block Masonry & Concrete existing structure and removal of Debris as per drawing & design complete	1	Lump Sump	51,000/-	51,000/-
6	Proving, laying, installation, testing & Commissioning of Electrical Luminaries LED SMD Lights by Philips or equivalent	8	Each	1695/-	13,560/-
7	Proving, laying, installation, testing & Commissioning of Electrical Luminaries LED COBI Lights by Philips or equivalent	12	Each	1313/-	15,756/-
8	Providing, laying, installing raised wooden Floor using 3.4" thick High density Plywood over Soft wood frame properly treated against Termite and having Carpet tile floor over wooden surface as per drawing and design & specification complete.	1150	SFT	949/-	1,091,350/-
9	Providing & applying wall matt finish in approved make and shade by ICI or equivalent complete as per drawing & design.	3250	SFT	63/-	204,750/-
1	3M or equivalent Cat6 Cable	4000	SFT	45/-	180,000/-
2	3M or equivalent I/O	116	Nos	935/-	108,460/-

M. HARIS QURESHI
External Member - PC
Procurement Specialist - HEJ
University of Karachi

DR. S.M FAISAL TRADAT
Chairman - PC
Assistant Professor & Program Director
IBA Karachi

M. MABROOR KHAN
External Member - PC
Admin Officer CEMB
University of Karachi

Syed Akbar Hussain
Member - PC
Manager Finance (Payable)
IBA Karachi



SYED WAJEEH ZAIDI
Member - PC
Manager IT
IBA Karachi

3	3M or equivalent Single shutter Phase plate with Back Box	58	Nos	503/-	29,174/-
5	3M or equivalent Cable manager	2	Nos	3953/-	7,906/-
6	8 Port PDU	1	Nos	4267/-	4,267/-
7	Channel Duct Adamjee or equivalent 25x25	30	Feet	69/-	2,070/-
	Channel Duct Adamjee or equivalent 40x40	150	Feet	101/-	15,150/-
8	Aluminum Plate	20	Feet	1633/-	32,660/-
	Flexible Pipe 1"	50	Feet	27/-	1,350/-
9	Flexible Pipe 1 1/2 "	20	Feet	43/-	860/-
10	Other accessories	1	Lumsum	15,000/-	15,000/-
	Cable laying and installation all related items I/O Punching Phase plate back box and tagging Aluminum plate fixing and cutting etc.	4000	Lumsum	10,000/-	10,000/-
Total Amount Inclusive Taxes				2,973,835/-	

M. MABROOR KHAN
External Member – PC
Admin Officer CEMB
University of Karachi

Total Amount in Words:

Two Million Nine Hundred
Seventy Three Thousand Eight Hundred
Thirty five Rupees Only/-.

3/5

Syed Akbar Hussain Kazmi
Member - PC
Manager Finance (Payable)
IBA Karachi

M. HARIQURESHI
External Member - PC
Procurement Specialist - HEJ
University of Karachi



SYED WAJEEH ZAIDI
Member - PC
Sr. Manager IT
IBA Karachi

DR. S.M FAISAL IRADAT
Chairman – PC
Assistant Professor & Program Director
IBA Karachi