

5.


Scope of Work / BoQ

Aluminum Works

S. #	Description	Quantity	Rates	Amount (Rupees)
1	<u>At Front of Library Main Gate</u> Providing and fixing 10 mm thick unbreakable hi impact poly carbonate sheet of approved quality and colour, including nut bolt screw fixing or riveting with existing aluminum frame and make joint water proof complete in all respect as per instruction of engineer including wastage, cartage, tools & plants etc. all complete. Size 432 SFT	1 job	283760/-	283760/-
2.a	<u>Near Library Reception Area</u> Providing, fabricating and fixing in position at any floor or height glass partition partially fixed with double openable doors as per site requirement with 12mm thick tempered glass with safety film gasket, locks, door closer, handle, sealant and all accessories including floor mounted hinge, complete in all respect & as per instruction of engineer. Size: 75 SFT	1 job	146250/-	146250/-
2.b	<u>Door</u> Providing, fabricating and fixing in position at any floor or height glass door openable double panelled with 12mm thick imported tempered glass with safety film gasket, locks, door closer, handle, sealant and all accessories including floor mounted hinge, complete in all respect as per instruction of engineer. Size: 40 SFT	1 job	78000/-	78000/-

MEMBER
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
Karachi
Syed Akbar
Finance
JBA, Karachi

CHAIRPERSON
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
DR. S.M. Faizal
Assistant Professor
JBA, Karachi



Stamp & Signature
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
Haris Qureshi
PPRA Advisor
HEP

3	<p>Ceiling Work</p> <p>Removal/cutting of existing false ceiling where necessary and providing and fixing new 2'x 2'x gypsum false ceiling, including G.I suspension system complete in all respect as per instruction of engineer. Top of curtain wall & cladding side wall where as required with matching paint. Size: 125 SFT</p>	1 job	24375/-	24375/2
4	<p>Door Frame Aluminum (Library First Floor at Staff Office)</p> <p>Providing and fixing door frame aluminium, 4"x2-1/2" aluminum frame with simple groove design, including fixing of existing wooden door shutter in aluminum frame including providing hinges, lock, polishing etc. as per instruction of engineer. (Door shutter is already available). Size: 30 SFT</p>	1 job	73500/-	73500/-
5	<p>Library Main Exit Gate</p> <p>Modification in existing main exit gate of library main campus library need to change from pull to push. Size 6.5 FT height and 6 FT width</p>	1 job	48750/-	48750/2
Total			= 664635/2 =	
SST			= 86402/2	
Total Amount			= 751037/-	

Total Amount in Words: Rs.

Seven lakh fifty one thousand three hundred and thirty seven only

Seven of

MEMBER (EXTERNAL)
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
Harris Qureshi
PPRA Advisor
HES



Stamp & Signature

MEMBER
CENTRAL PURCHASE COMMITTEE
INSTITUTE OF BUSINESS ADMINISTRATION
KARACHI
F. Hussain
PPRA Advisor
KARACHI

1/1