

INSTITUTE OF BUSINESS ADMINISTRATION KARACHI
ESTABLISHMENT OF NEURO LAB AT AMAN CED BUILDING MAIN CAMPUS KARACHI
PRICED BILL OF QUANTITY/ ENGINEER'S ESTIMATE

S. No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Wood Works					
1	Providing, installing in position Work station using laminated ply wood ¾" (20mm) thick on 2 nd class white soft wood ,using proper press with glue as per size and design approved. The bidder shall submit drawing /sketch along with bid along with complete description of the wood proposed to be used. All the wood and board shall be properly treated with anti Termite Treatment as per specification and direction.	5	Each		
2	Providing & laying in position Table with Island using laminated ply wood board ¾" (20mm) using, white soft wood frame with proper glued as per specification and drawing. The bidder shall submit sketch /drawing and specification or description of the material proposed to be use ,along with bid for the proposed article. All the wood and board shall be properly treated with anti Termite Treatment as per specification and direction.	1	Each		
3	Providing ,Laying installation in position Plain Table as per drawing using laminated ply wood board ¾" (20mm) thick over , white soft wood frame with proper glued as per specification complete in all respect.	1	Each		
Civil Work					
4	Providing & applying Water based Emulsion Paint on walls in approved make and shade as per specification	800	SFT		
5	Demolishing & Removal of Existing wooden wall Panel as per Direction.	1	Lumsum		
Electrical Work					
6	Providing & Laying Electric Cable works, Boards & Switches & Networking as per requirements drawing and Direction using Wire/ Cable by Pakistan Cable or Equivalent as per approval complete as per specification (Pakistan cable, aqua board, switch board)	484	SFT		
ICT Work					
7	Corning Cat 6, UTP, PVC, 4 Pairs, 305 Meter Coil & 1000 RFT Box	1000	Feet		
8	Corning / 3M Cat 6 RJ45 - K6 I/O Jack, UTP	26	Nos		
9	Corning / 3M 24 Ports Patch Panel Without IOS – Unloaded	1	Nos		
10	Corning / 3M Single Gang shutter Phase plate With back Boxes	13	Nos		
11	Corning / 3M Cable manager	1	Nos		
12	4U Rack With Fan	1	Nos		
13	Corning / 3M Patch Cord 1m	13	Nos		
14	Corning / 3M Patch Cord 3m	13	Nos		
15	Adamjee Channel Duct 25x38	80	Feet		
16	Aluminum Channel/Plate	40	Feet		
17	Other accessories for channel duct Installation, Screws, Gage Nuts, wooden Gitti,Cable Ties,Raval Bolts, Flexible Pipe etc.	1	Lumsum		
18	Cable laying and channel duct installation all related items I/O Punching Phase plate back box and Tagging, Rack Fixing Management, Aluminum plate fixing fixing etc.	1000	Feet		
				Total Cost	