6. Bill of Quantity

SCOPE OF WORK Dampa Ceiling Works at Aman CED Washroom

S#	Description	Unit	Quantity	Rate	Amount
1	Provide & Fix Dampa Ceiling Aluminum				
	Providing & fixing dampa ceiling aluminum, of china make 2' x 2' tiles ceiling, laid into a G.I T & L Angle 1" x 1" frame work, plump, rods, hanger clips, jointing clips and G.I Wire etc suspended from the structural ceiling, complete in all respect as per Site requirement, approved manufacturer and specifications. Note: This item includes the removal of existing False Ceiling	Sft	1880	399	550620
2	Provide & Fix Powder Coated Access Panel (18" x 18") in Gypsum Ceiling				
	Providing, fixing & cutting hole (18" x 18") in Gypsum ceiling for fabrication of bottom hinged Powder Coated Metal Pan, Access Panel comprising of matt white powder coated aluminum T-Frame 580 x 580mm, fitted flush to ceiling with and including screw fixing through frame, complete in all respect as per Site requirement, approved manufacturer and specifications.	Each	25	5000	125000
Total Amount				675620	
SST				INCLUSIVE OF TAXES	
Grand Total Amount with All Taxes				675620	

Note: Site visit is mandatory.

Grand Total Amount Rupees in Words: Rs. SIX LAC SEVENTY FIVE THOUSAND

SIX HUNDRED AND TWENTY RUPEES ONLY

M.HARIS QURESHI

Manager Finance (Fayable)
IBA Karackii

DR. SHAHID MIR

thairman - PC

Assistant Professor - Management

Stamp & Signature

Page 14 of 22

Sh