

# BILL OF QUANTITY

Annexure 'A'

## SCOPE OF WORK

### MAIN PARKING AREA

S. No.	Description	Unit	Quantity	Rate	Amount Inclusive of taxes
1	Dismantling of Existing Paved Area PCC including disposal of unusable debris to some designated place	2200	Cft	65/2	143000/2
2	Removal of existing blocks and shifting to some designated place as per direction	3000	Sft	18/2	54000/2
3	Providing, laying in position 18"x12"x6" Kerb Block min 3000 PSI cylindrical strength conc. Manufactured by Banu Mukhtar, Envicrete, Megncrete or equivalent as approved by Engineer Incharge including excavation, Concrete 1:2:4 benching etc complete as per specification.	1560	Rft	595/2	928,200/2
4	Refixing &, laying in position 18"x12"x6"/ 12"x12"x6" existing Kerb Block min 3000 PSI cylindrical strength conc. or as approved by Engineer Incharge including excavation, Concrete 1:2:4 benching etc complete as per specification.	2500	Rft	85/2	212500/2
5	Providing , laying & filling granular earth as per drawing & design including levelling & compaction complete as per direction.	8500	Cft	58/2	493000/2
6	Proving ,& laying Quadra Paver 80mm thick 8000psi manufactured by Envicrete, Bannu Mukhtar, Megnacrete or equivalent in natural color laid over 2" thick Stone dust Khaka including levelling, grading, compaction , watering jointing etc complete as per direction	3500	Sft	249/2	871500/2
7	do- but pigmented in approved color	2500	Sft	287/2	717500/2

IBAL SHAH AND CO.

Proprietor

DR. SHAH MIR  
Chairman - PC  
Assistant Professor - Management  
IBA Karachi

IBAL SHAH AND CO.

Proprietor

M. HARIS QURESHI  
External Member - PC  
Procurement Specialist - HEJ  
University of Karachi

Stamp of IBAL SHAH AND CO.

Page 80

Proprietor

Syed Akbar Hussain Kazmi  
Member - PC  
Manager Finance (Payable)  
IBA Karachi

8	Refixing in position of existing paver present at site including providing ,laying, levelling, compaction of Stone dust as per direction.	5500	Sft	85/-	467500/-
9	Providing ,laying in position Rubber Wheel Stopper manufactured by M/s Polu Craft or equivalent as per manufacturer's direction complete.	264	Nos	2700/-	712800/-
10	Providing, laying in position Rubber Speed Humper including Middle section, size 20"x15"x2" in Black & Yellow Combination Manufactured by M/S Poly Craft or equivalent and fixed in position as per manufacturers recommendation and per specification.	192	Nos	3700/-	710400/-
11	do- but end cap	8	Nos	2700/-	21600/-
12	Providing & laying 2" wide Road Marking using Road Paint oil/rubber in yellow or Specified Colour manufactured by M/S Berger or Equivalent.	3000	Rft	18/-	54000/-
13	Providing & fixing high performance Road Studs 90mmx103mmx18mm sizes & colour manufactured by Poly Craft or equivalent as approved by Engineer Incharge.	550	Nos	350/-	192500/-
14	Providing & laying Black & Yellow colour Enamel Paint manufactured by Berger or ICI or equivalent in two coats on Kerb Block as per direction.	3510	Sft	25/-	87750/-
15	Providing and laying concrete 3000 PSI cylindrical strength including levelling and curing etc complete.	2000	Cft	245/-	490000/-
16	Providing and laying concrete 1000 PSI cylindrical strength including levelling and curing etc complete.	1000	Cft	225/-	225000/-
Total Amount Inclusive of Taxes (Annexure 'A')				=6381250/-	

Syed Akbar Hussain Kazmi  
Member - PC  
Manager Finance (Payables)  
IBA Karachi

DR. SHANID MIR  
Chairman - PC  
Assistant Professor - Management  
IBA Karachi

M. HARI QURESHI  
External Member - PC  
Procurement Specialist - NEJ  
University of Karachi

IQBAL SHAH AND CO.

Proprietor

IQBAL SHAH AND CO.

Stamp & Signature

**SCOPE OF WORK****ADAMJEE ACADEMIC BLOCK**

S. No.	Description	Unit	Quantity	Rate	Amount Inclusive of taxes
1	Dismantling of Existing Paved Area PCC including disposal of unusable debris to some designated place	1800	Cft	25 1/2	45000/-
2	Providing, laying in position 18"x12"x6" Kerb Block min 3000 PSI cylindrical strength conc. Manufactured by Banu Mukhtar, Envicrete, Megncrete or equivalent or as approved by Engineer Incharge including excavation, Concrete 1:2:4 benching etc complete as per specification.	1600	Rft	595 1/2	952000/-
3	Providing, laying & filling granular earth as per drawing & design including levelling & compaction complete as per direction.	4000	Cft	58 1/2	232000/-
4	Providing, & laying Quadra Paver 80mm thick 8000psi manufactured by Envicrete, Bannu Mukhtar, Megncrete or equivalent in natural colour laid over 2" thick Stone dust Khaka including levelling, grading, compaction, watering jointing etc complete as per direction	2000	Sft	249 1/2	498.000/-
5	do- but pigmented in approved colour	750	Sft	285 1/2	213750/-
6	Refixing in position of existing paver present at site including providing, laying, levelling, compaction of Stone dust as per direction.	850	Sft	85 1/2	72250/-
7	Providing, laying in position Rubber Wheel Stopper manufactured by M/s Polycraft or equivalent as per manufacturer's direction complete.	96	Nos	2700 1/2	259200/-

**DR. SHAHID MIR**Chairman - PC  
Assistant Professor - Management  
IBA Karachi**IQBAL SHAH AND CO.**

Proprietor

**M. HARI QURESHI**  
External Member - PC  
Procurement Specialist - HEJ  
University of Karachi**IQBAL SHAH AND CO.**

Proprietor

Stamp &amp; Signature

Akbar Hussain Kazmi  
Member - PC  
Manager Finance (Payable)  
IBA Karachi

8	Providing, laying in position Rubber Speed Hump including Middle section, size 20"x15"x2" in Black & Yellow Combination Manufactured by M/s Poly Craft or equivalent and fixed in position as per manufacturers recommendation and per specification.	96	Nos	3700/-	340000/-
9	do- but end cap	4	Nos	2700/-	10800/-
10	Providing & laying 2" wide Road Marking using Road Paint in yellow oil/rubber or Specified Colour manufactured by M/S Berger or Equivalent.	1500	Rft	18/-	27000/-
11	Providing & fixing high performance Road Studs 90mmx103mmx18mm sizes & colour as approved by Engineer Incharge manufactured by Poly Craft or equivalent as approved.	260	Nos	350/-	91000/-
12	Providing & laying Black & Yellow colour Enamel Paint manufactured by Berger or ICI or equivalent in two coats on Kerb Block as per direction.	850	Sft	25/-	212500/-
Total Amount Inclusive of Taxes(Annexure 'B')				=2953500/-	

Syed Akbar Hussain Kazmi  
Member - PC  
Manager Finance (Payable)  
IBA Karachi

DR. SHAHID MIR  
Chairman - PC  
Assistant Professor - Management  
IBA Karachi

M. HAFIS QURESHI  
External Member - PC  
Procurement Specialist - HEJ  
University of Karachi

Jadid

**IQBAL SHAH AND CO**

Proprietor

Stamp & Signature

**IQBAL SHAH AND CO.**

Proprietor

Grand Total Amount Inclusive of Taxes of Annexure A+B


Rs. 9334750/-


Grand Total Amount in Words of Annexure A+B

Rupees: NINE MILLION THREE HUNDRED

THIRTY-FOUR THOUSAND SEVEN HUNDRED SIXTY RUPEES

  
Syed Akbar Hussain Kazmi  
Member - PC  
Manager Finance (Payable)  
IBA Karachi

  
M. HARIS QURESHI  
External Member - PC  
Procurement Specialist - HEJ  
University of Karachi

  
DR. SHAHID MIR  
Chairman - PC  
Assistant Professor - Management  
IBA Karachi




IQBAL SHAH AND CO.

Proprietor

IQBAL SHAH AND CO.

Proprietor

  
Stamp & Signature  
Page 84



