

6. Bill of Quantity

SCOPE OF WORK

Dampa Ceiling Aluminum Works in Adamjee Building

S#	DESCRIPTION	QUANTITY	UNIT	RATE	AMOUNT
1	Providing & fixing dampa ceiling aluminum of DOUGLAS or approved equivalent make 2' x 2' tiles ceiling, laid into a G.I T & L Angle 1" x 1" frame work, plump, rods, hanger clips, jointing clips and G.I Wire etc suspended from the structural ceiling, complete in all respect as per Site requirement, approved manufacturer and specifications. Note: This item includes the removal of existing Gypsum Ceiling and refixing of existing available Panels of HVAC in their position.	3020	sft	518	1,564,360/-
2	Removal & Re-Lay of Existing Dampa Ceiling Tiles. Removing of existing Dampa false ceiling tiles including re-lay on the designated place after cleaning / repairing, complete in all respect as per drawing and as directed by the Engineer. Note 1: When pricing the rate of this item Contractor is requested to visit the site and ascertain himself the amount of works and consider all cost of operations, procedures and requirement to complete the work with mark-up, no additional payment shall be made separately in this account). Note 2: It is the responsibility of contractor to note and mark the repair & re-lay part of existing dampa ceiling and inform the Client Engineer for measurement of repair & re-lay area. Note 3: Site visit is mandatory	6000	sft	19	1,14,000/-
Total					1,678,360/-
SST					Inclusive
Grand Total Amount					1,678,360/-

Grand Total Amount Rupees in Words: Rs. Sixteen lacs

Seventy eight thousands Three hundred & sixty = 1,678,360/-

(Signature)
Syed Akbar Hussain Kazmi
 Member - PC
 Manager Finance (Payable)
 IBA Karachi

M. HARIS QURESHI
 External Member - PC
 Procurement Specialist - IBA
 University of Karachi

(Signature)



Stamp & Signature

(Signature)
DR. SHAHID QUR
 Page 14 of 22
 Chairman - PC
 Assistant Professor - Management
 IBA Karachi