

6. Bill of Quantity

SCOPE OF WORK

Supply & Installation of Electric Poles at IBA Staff Town

S.#	DESCRIPTION	UNIT	RATE	QTY	AMOUNT
1	Jungle Clearance and removing within 100 Rft.	Sft	20/-	2000	40000-0
	Construction of RCC foundation as per following specification for 7.00 Meter tubular pole. Excavation of soft /hard soil Size 3'-0"x3'-0"x4'-6". Stone soling 3'-0"x3'-0"x0'-6". Making Lean Concrete 1:4:8. 6" thick Length of MS Bolt 5'-6" ( 3/4" dia ) 4Nos & making threads on MS rods Template 16"x16" x1/4". Rings 3/4" dia round bar 4Nos welded to MS rod RCC foundation ratio 1:2:4 -SR Cement Concrete with appropriate size 2'-0"x2'-0"x4'-6"	Each	16000/-	20	320000-0
3	Providing & fixing of Hot Dipped Galvanized Steeped Tubular Pole with double /Single Arms to fix light fixtures fixed on precast foundation with the help of hydraulic crane or manual Labour as per following specification. 1. Overall length = 7.0 meter 2. Section A = 4.0 Meter Outer dia 114.3mm and thickness 3.65mm 3. Section B = 1.5 Meter. Outer dia =88.4mm and thickness 3.25 mm 4. Section C = 1.5mm .Outer dia 75mm and thickness = 3.25mm 5. Minimum wt. of Pole = 58.55 Kg 6. Base Plate 400mmx400mmx10mm 7. Anchor Bolt = M18x400 4 Nos 8. Stiffners 130x260x20mm 9. Opening window in the pole of required size with LN Key provision. Jamal/Bashir /IIL/Steelx Equivalent	Each	35000/-	20	700000-0

MEMBER (EXTERNAL)  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Hussain Qureshi  
Advisor HET


MEMBER  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Syed Akber, Hussain Kazmi  
Finance IBA, Karachi

MEMBER (EXTERNAL)  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Maksood Khan  
Admin Officer  
CEMB, UOK

MEMBER  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Wajeeh Zaide  
St. Manager  
WIT- IBA  
Karachi

CHAIRPERSON  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Dr. S.M. Faisal Iradat  
Assistant Professor  
IBA - Karachi

Syed Rahim Shah & Brothers  
Proprietor





S.#	DESCRIPTION	UNIT	RATE	QTY	AMOUNT
4	Providing & Laying main or sub main PVC insulated and PVC with 4core copper conductor 300 /500 volts size 6mm sq. in 2" PVC conduit. This rate include in all type of excavation an d back filling of Trenches.	R Mtr.	1300/-	1270	1,651,000-0
5	Providing & Laying main or sub main PVC insulated and PVC with 3core copper conductor 300 /500 volts size 2.5mm sq. Item No 65 Page 8	R Mtr.	400/-	350	140,000-0
	Providing & Fixing of flood light 250 Watts (HPIT) having IP65 classification with 250 W lamp, choke, capacitor, ignitor & Internal wiring complete in all respect at the height of 40' with the help of hydraulic crane & manual labour as per site requirement and instruction.	Each	12000/-	20	240,000-0
10	Repair of existing Pole foundation as per direction & Requirements.	Each	3000/-	10	30,000-0
Total					3,121,000-0
SST					Inclusive
Grand Total with Taxes					

MEMBER (EXTERNAL)  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
ifaz's Qureshi  
PPRA Advisor

MEMBER (EXTERNAL)  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Mabsoob Khan  
Admin Officer  
C-EMIS, WOK

Grand Total Amount Rupees in Words

Thirty One lacs  
Twenty One Thousands Only /-

**Note**

- The rate is inclusive of all type of labour material, tools & plants etc.
- The rate is inclusive of all type of taxes and levies.

MEMBER  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI

Wajeeh Zaidi  
Sr. Manager  
IBA, Karachi

CHAIRPERSON  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI  
Dr. SM Faisal Iqbal  
Assistant Professor  
IBA, Karachi

Syed Rahim Shah & Brothers  
Proprietor

MEMBER  
CENTRAL PURCHASE COMMITTEE  
INSTITUTE OF BUSINESS ADMINISTRATION  
KARACHI

Syed Akbar Hussain  
Kazmi  
Finance IBA, Karachi

Stamp & Signature