

Institute of Business Administration (IBA)

Main Campus

Project: Student Center, IBA Main Campus

Works: Nikasi Pipes & Carpentry Work in Jam Room

**Engineer's
Estimate**

1. Item No.	2. Description of Item	3. Quantity	4. Unit
1	<p><u>Facility Sanitary Sewerage.</u> <u>Repair of Nikasi Pipe Lines.</u> Supply and lay UPVC pipes of Dadex or approved equivalent, Nikasi for soil, waste and vent system including specials such as P-Trap, tees, bends, plugs, reducers, etc. with solvent cement jointing / rubber ring push fit jointing method including removal of existing burnt lines & specials, cutting holes in masonry or concrete in walls, floor and in slab, making good the same, complete in all respect as per drawing, specification and as directed by the Engineer.</p> <p>a 50 mm diameter. b 75 mm diameter. c 110 mm diameter.</p> <p>Note: This item includes the removal of existing pipe & fittings at any height.</p>	1.0	Job
2	<p><u>Fixing & Repairing of MDF Lasani Sheet & Wood Frame</u> Supply & fix in position Lasani MDF Sheets (12mm to 16mm) thick & Wooden frame at ceiling as per size and dimension & as per site condition along with fixing of wood architrave upto 6 inch wide with all hardware & fittings, paint as required complete in all respect as directed by the Engineer incharge.</p>	1.0	Job