

INSTITUTE OF BUSINESS ADMINISTRATION ( IBA ) KARACHI								
IBA HOSTEL MAIN CAMPUS KARACHI.								
BILL OF QUANTITIES FOR SUPPLY, FABRICATION & ERECTION OF MAIN EMERGENCY GATE AT IBA HOSTEL								
S. No.	Description	Qty	Unit	Material Rate Rs.	Material Cost Rs. (3x5)	Installation Rate Rs.	Installation Cost Rs. (3x7)	Total Amont Rs. (6+8)
1	2	3	4	5	6	7	8	9
A	<b>EMERGENCY MAIN GATE</b> Supply,Fabrication, & Erection in position at site of Main Emergency Gate average size 16-0" x 7'-9" Complete as per existing Main Gate and as per specification. The Gate comprises of 3"x3" Rectangular Pipe 16 SWG 2"x1" rectangular tube door panel frame 16 SWG thickness with intermediate pipe support of same size and with locking arrangements including grinding , painting with Enamel Paint in approved shade and colour and transportation, loading, unloading fixing in position complete as per direction complete and fixing in existing RCC column but cutting holes for fixing hold fasts as per direction complete in all respects.	124	SFT	0	0	0	0	0
	Sub-Total Carried to Summary							0
	Sub-Total Carried to Summary							