

**SCOPE OF WORK**

**BOQ of Floor Tiles Fixing**

**IBA 3<sup>rd</sup> Floor at Aman Tower City Campus (ONE JOB)**

S. No.	Description	Qty	Unit	Rate	Amount
1	providing and fixing 24x24 master tile matt finish of approved sample and color for flooring with 1:4 cement sand mortar base of required thickness 2" setting the tiles with cement mortar and making proper, skirting and making proper grooves with spacer and matching with color grout as approved by the maintenance manage	1400	Sqft		
	<b>Total Amount (Approximate)</b>				

Note:

1. IBA Maintenance Department reserve the right to cancel / amend; increase or decrease scope of work under different headings.