

**Comparative Statement**

**Fixing of Pavers and Kerb Blocks in Front of Office & Stores at IBA Main Campus**

**Tender # CW/18/24-25**

S. #	Items	Unit	Qty	M/s M.G. Construction		M/s M.M. Constructions		M/s World Wide Engineer's Associates		M/s Habib Contractors Company		M/s Mahfooz Nabi Shaikh & CO.		M/s Munawar Ali Khaskheli		M/s Kamal Khan & Brothers		M/s FBC Construction Company		M/s Creative Contractors		M/s Uni Enterprises					
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
<b>SCHEDULE RATE ITEMS BASED ON CSR (SINDH) 2024</b>																							Rejected, due to envelop not sealed		Non-Responsive, did not meet the eligibility criteria		
1	<b>Cutting of Road</b>																										
	Dismantling and removing road metalling. Refer Item no. 51 Page No. 21 Chapter No. 2 Notes: Rates for all finished works include the removal of surplus debris un-used material and by-product.	P.Cft	7269.58	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79	26.93	195,769.79						
2	<b>CC Pavers (Red Pigmented)</b>																										
	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city /quddra / cobble shape with pigment, having strength b/w 5000 PSI to 8500 PSI i/c filling the joints with hill sand over a bed of 2" thick hill sand or stone dust and laying and compacting in specified manner/ pattern and design etc complete. Refer Item no. 70 Page No. 50 Chapter No. 8	P.Sft	1066.70	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74	242.26	258,418.74						
3	<b>CC Pavers (Natural Colour)</b>																										
	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 80 (mm) of city /quddra / cobble shape with natural colours, having strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand over a bed of 2" thick hill sand or stone dust and laying and compacting in specified manner/ pattern and design etc complete. ( PSI 5000 to 8500e /Tameer Works or Equivalent manufacturer Refer Item no. 69 Page No. 50 Chapter No. 8	P.Sft	13476.95	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89	227.51	3,066,140.89						
4	<b>Kerb Stone (Natural Colour)</b>																										
	Providing & fixing Precast Edge Block 3750 PSI Industrial Made Size 6 inches thick x 12 inches long x 18 inches high including the cost of Cartage, excavation, form Work for haunching, 1450 PSI lean concrete, 2250 PSI concrete for haunching, 1:4 cement sand mortar. Refer Item no. 39(14) Page No. 221 Chapter: Schedule of Rates for Highways Works-2024.	P.Rft	450.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00	678.38	305,271.00						
<b>Total Amount Of Scheduled Based Items</b>					3,825,600.43		3,825,600.43		3,825,600.43		3,825,600.43		3,825,600.43		3,825,600.43		3,825,600.43		3,825,600.43		3,825,600.43						
Premium/Rebate ( %)					784,248.09		765,120.09		765,120.09		612,096.07		573,840.06		383,439.92		153,024.02		38,256.00								
Total amount including premium/rebate					3,041,352.34		3,060,480.34		3,060,480.34		3,213,504.36		3,251,760.36		3,442,160.51		3,672,576.41		3,863,856.43								
ADD 15% SST					456,202.85		459,072.05		459,072.05		482,025.65		487,764.05		516,324.08		550,886.46		579,578.46								
<b>Grand Total Amount (with 15% SST)</b>					3,497,555.19		3,519,552.39		3,519,552.39		3,695,530.01		3,739,524.42		3,958,484.58		4,223,462.87		4,443,434.89								

**DR. SHAHID MIR**  
Chairman - PC  
Assistant Professor - Management  
IBA Karachi

**MARIS QURESHI**  
External Member - PC  
Procurement Specialist - HEJ  
University of Karachi

**Syed Akbar Hussain Kazmi**  
Member - PC  
Manager Finance (Payable)  
IBA Karachi